

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 28W	E7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 16 T 50N R 28W	3
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on E7 09/13/2012  
3 09/12/2012 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E7) Corner common to Sections 16-17-20-21. 1852 - Established by A.B.Wood, Deputy Surveyor, on the  
corrected E-W centerline of this township. Set post. S.Pine 10" S50W 6 links, S.Pine 6" N53E 11  
links. July 14, 1947 - Field notes of James J. Heilala, Marquette County Road Commission, in Field  
Book 533, state: S.Pine 10 S50W 6 links and S.Pine 6 N53E 11 links are both down but scribe marks are  
distinct. Iron pipe and pine post. Set new B.T.s Norway Pine N11W 42.2', J.Pine 6" S21W 59.9'.

(3-Sec. 16) North 1/16 corner between Sections 16 and 17. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E7) Found a 1.5" ID iron pipe, projecting 9" a.g. in which was found a 1" ID iron pipe, overall  
height 4 ft. The Norway (Red) Pine NBT marked in 1947 was found at record bearing and distance, in  
good condition, now blazed high and low, with a duplex measuring nail in the side. Also found three  
other nearby trees, marked in a similar fashion, by persons unknown, as witnesses. Accepted the  
monument as a careful and faithful perpetuation of the position of the original corner.

(3-Sec. 16) Established the position for the corner midway and on the Section line between Section  
corner 1315.72' north and Quarter corner 1315.72' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E7) Found 1"ID I.pipe in 1.5" ID I.pipe and  
set plastic cap "Mich DNR PS 33986" in top.  
Found duplex nail in the side of blazed trees:  
18" R.Pine N05W 42.45' overgrown. 1947 NBT  
9" J.Pine N47E 46.85'  
6" R.Pine S33E 13.45'  
14" J.Pine S42W 8.1' overgrown  
Bearings are magnetic.

(3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
6" W.Birch S85E 11.75' mrkd "1/16S BT"  
3" Oak S11W 29.45' do  
6" J.Pine S68W 25.2' do  
6" Oak N53W 48.45' do  
Set sq'd cedar post adjacent.  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 10/08/2012

For the Michigan Department of Natural Resources, Forest Resources Division

