

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 28W	G7
	T R	
	T R	
2. Property Controlling in Section	S 16 T 50N R 28W	5
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 5 09/11/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G7) Corner common to Sections 15-16-21-22. 1852 - Established by A.B.Wood, Deputy Surveyor. Set
post on corrected E-W centerline of this township. Fir 8" N80E 12 links, Spruce 10" N42W 22 links.
July 17, 1947 - Notes of James J. Heilala, Marquette County Road Commission, in F.B. 601 P.125 state
"A post on a cross line. Found no BTs". 1992 - Paul N. Bressette, PS found post and Celotex
location poster dated 1957.

(5-Sec. 16) North 1/16 corner, Section 16. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G7) The original post and accessories were not recovered. Found a 3/4" ID iron pipe in the former
place of a squared post, now down and rotting, with Celotex location poster affixed. Found 3
adjacent trees, marked as witnesses by persons unknown, with small side blazes into which had been
driven duplex measuring nails. The trees were found painted and the nails were well grown in,
indicating the work was not recent. The position of the pipe was confirmed by measurement to be that
of the post found by Bressette in 1992. I accepted the pipe as the best available evidence of the
position of the corner. Measurements to adjacent Section corners north and west were found to be
5205.88' and 5289.72', respectively.

(5-Sec. 16) Established the position for the corner midway and on a straight line between Quarter
corner 1308.61' north and the Center of Section 16 1308.61' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G7) Drove a 5/8"x24" rebar w/plastic MDNR cap
into the found 3/4" pipe.
Found duplex nails in, and scribed:
15" W.Pine S51W 12.45' mrkd "S21 NBT"
11" W.Pine S16W 15.4' do
7" B.Spruce N87E 15.3' "S15 NBT"
Set measuring nail with MDNR tag in the side of:
7" W.Pine N06E 32.8' mrkd "S15 NBT"
Set sq'd cedar post adjacent.
Bearings are magnetic.

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
7" Oak N20E 19.4' mrkd "1/16S BT"
7" Oak N88E 18.4' do
9" Maple S05E 5.3' do
4" Oak S77W 19.95' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/08/2012

For the Michigan Department of Natural Resources, Forest Resources Division

