

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 28W	G6
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 16 T 50N R 28W	F6
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on G6 08/10/2012
F6 09/11/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G6) Quarter corner common to Sections 15 and 16. 1852 - Established by A.B.Wood, Deputy Surveyor,
midway and on the Section line between Section corners 40.00 chains north and south. Set post.
Y.Birch 12" N52E 33 links, Fir 14" S67W 18 links. The notes state W.Pine 20" at 49.68 chains, or
9.68 ch. north of the corner. Found no subsequent record.

(F6) Center of Section 16. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G6) The original post and accessories were not recovered. Found no evidence of the W.Pine line tree
at 49.68. Found no acceptable evidence of the position of the original corner on the ground.
Reestablished the position for the corner midway and on the Section line between Section corners
2602.93' north and south. I also searched 40.0 chains north of G7 and 40 chains south of G5, and
found no evidence of the original corner. From the position thus established, a sq'd 8" W.Pine,
marked by persons unknown, apparently for an approximate corner, is S56W 3.3' distant.

(F6) Established the position for the corner at the intersection of straight lines connecting
opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
9" Maple N14W 10.75' mrkd "1/4S NBT"
9" Maple N30E 5.4' do
8" W.Pine S54E 9.75' do
10" Oak in clump S43W 17.85' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

(F6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
7" B.Spruce N04W 13.2' mrkd "C1/4 BT"
7" Oak S69E 14.55' do
7" W.Pine S05E 29.2' do
7" B.Spruce S77W 7.1' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/08/2012

For the Michigan Department of Natural Resources, Forest Resources Division

