

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 29W	F9
	T R	
	T R	
2. Property Controlling in Section	S 18 T 52N R 29W	14
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

I, Stephan J. Szyszkoski, in a field survey on 14 03/26/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F9) Quarter corner common to Sections 21 and 28. 1846 - Established by Deputy Surveyors Hubbard and Ives. Set post. Lynn 8" S26W 09 links, Sugar 4" N20W 08 links. 1939 - Norman T. Thompson RLS ran and marked the south line of Section 21 stating about F9: "No B.T. [cor.] is cor. of fence running S & E. Set hem. post. Blazing line on fence east..." No NBTs noted in the 1939 notes. Found no subsequent record.

(14-Sec. 18) South 1/16 corner between Sections 17 and 18. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F9) The original post and accessories were not recovered. Found scraps of barbed wire fencing on the surface of the ground running about S27W from a undefined intersection with a few pieces of fencing found running easterly. The apparent intersection does not fit well with the record, it being nearly 80' S76E from the proportionate position. The area has been heavily logged in the past. I am not confident that the position estimated to be the fence intersection marks the 1939 position and do not accept it as marking the position of the corner. Reestablished the position for the corner midway and on the Section line between Section corners 2653.02' east and west, being proportionate to the original record.

(14-Sec. 18) Established the position for the corner midway and on the Section line between Section corner 1319.37' south and Quarter corner 1319.37' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
6" Ironwood N53E 23.2' mrkd "1/4S NBT"
14" Hemlock S78E 17.35' do
7" Hemlock S63W 10.05' do
9" Y.Birch N34W 24.6' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

(14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
5" Poplar N36E 10.6' mrkd "1/16S BT"
7" Sugar S66E 18.6' do
4" Sugar S08W 16.9' do
3" Maple N73W 13.8' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 07/10/2012

For the Michigan Department of Natural Resources, Forest Resources Division

