

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 29W T 52N R 29W T R	E11 E10
2. Property Controlling in Section	S T R S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on E11 05/12/2012
E10 05/21/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E11) Corner common to Sections 28-29-32-33. 1846 - Established by Deputy Surveyors Hubbard and
Ives. Set post on steep side of hill descending south. Y.Pine 4" S18W 35 links, W.Pine 16" N75E 18
links. Found no subsequent record.

(E10) Quarter corner common to Sections 28 and 29. 1846 - Established by Deputy Surveyors Hubbard
and Ives. Set post. Sugar 10" S55W 27 links, Hemlock 20" N29E 25 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E11) The original post and accessories were not recovered. Found no acceptable evidence of the
position of the original corner on the ground. Reestablished the position for the corner by double
proportionate measurement to the original record between corners 5252.49' west (5262.8' GLO),
5230.21' north (5280' GLO), 5296.24' east (5306.4' GLO), and 2615.12' south (2640' GLO). The
position falls on a rock south-sloping side hill and was marked with a chiseled "X" in the rock.

(E10) The original post and accessories were not recovered. Found no acceptable evidence of the
position of the original corner on the ground. Reestablished the position for the corner midway and
on the Section line between Section corners 2615.11' north and south, being proportionate to the
original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E11) Chiseled an "X" in surface bedrock.
Set two reference monuments being 5/8" rebar
8" to 10" long driven into cracks in the
rock, and encased in concrete and a 1"ID
I.pipe with MDNR cap, N51W 7.68' and
N78E 7.71' distant. Set measuring nail with
MDNR tag in the side of:
12" W.Pine S61E 24.0' mrkd "S33 NBT"
6" W.Pine S42W 15.5' "S32 NBT"
Cedar post set S10E 5.1' distant. Brgs magnetic.

(E10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
15" Hemlock S43E 11.5' mrkd "1/4S NBT"
12" Hemlock S02E 9.0' do
8" Maple N84W 28.9' do
9" Hemlock N04W 8.4' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 07/10/2012

For the Michigan Department of Natural Resources, Forest Resources Division

