

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 52N R 29W	G10
	T 52N R 29W	D11
2. Property Controlling in Section	T	
	T	
	T	
3. Miscellaneous Property in Sec.	S	
	S	
	S	
	S	
4. Lot No.	Recorded Plat	
5. Private Claims		

I, Stephan J. Szyszkoski, in a field survey on G10 05/17/2012 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G10) Quarter corner common to Sections 27 and 28. 1846 - Established by Deputy Surveyors Hubbard and Ives. Set post. Ironwood 5" S60W 23 links, Y.Birch 14" N60E 30 links. Found no subsequent record.

(D11) Quarter corner common to Sections 29 & 32. 1846 - Established by Deputy Surveyors Hubbard and Ives. Set post. Hemlock 14" S50E 04 links, Hemlock 12" N33E 21 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G10) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner midway and on the Section line between Section corners 2627.58' north and south, being proportionate to the original record.

(D11) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the position for the corner midway and on the Section line between Section corners 2626.25' east and west, being proportionate to the original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
8" Sugar N34E 3.3' mrkd "1/4S NBT"
15" Oak S32E 33.0' do
14" Hemlock S75W 20.1' do
6" Oak N21W 19.45' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(D11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
8" dbl Maple N44E 19.6' mrkd "1/4S NBT"
4" Hemlock S40E 1.9' do
7" Hemlock S85W 3.3' do
5" Hemlock N58W 7.75' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 07/10/2012

For the Michigan Department of Natural Resources, Forest Resources Division

