

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 29W	E9
	T R	
	T R	
2. Property Controlling in Section	S 16 T 52N R 29W	15
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Stephan J. Szyszkoski, in a field survey on E9 05/03/2012
15 03/27/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E9) Corner common to Sections 20-21-28-29. 1846 - Established by Deputy Surveyors Hubbard and Ives.
Monument not noted but most certainly a wood post. Hemlock 22" S73E 21 links, Hemlock 18" N25W 32
links. 1939 - Notes of Norman T. Thompson RLS state as to this corner: "S.W. cor. [Sec. 21]. No
B.T. Bal. post set 11-29-38 by D.W.O. and N.T.T." No NBTs given. Feb. 2002 - The undersigned found
and accepted a 1"ID I.pipe projecting 2' a.g. at the corner position.

(15-Sec. 16) West 1/16 corner between Sections 16 and 21. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E9) The original post and accessories were not recovered. Found a 1"ID Iron pipe projecting about
2' a.g. with mushroomed top. Distances to adjacent corners were found as follows: 5271.05' west to a
2.5" OD I.pipe, a perpetuation of the original position at C9 (5269.4' GLO); 5319.87' north to a 1"ID
I. pipe of record at E7 (5280' GLO); 5306.04' east to an MDNR monument of record at G9 (5311.7' GLO);
and 7845.31' south to an MDNR monument perpetuating the original position of E11 (7920.0' GLO). I
accepted the pipe at E9 as marking the position of the 1938 N.T.Thompson reestablishment of the
position of the original corner.

(15-Sec. 16) Established the position for the corner midway and on the Section line between Section
corner 1319.58' west and Quarter corner 1319.58' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E9) Found 1"ID I.pipe and placed plastic MDNR
survey cap PS 33986 inside.
Set measuring nail with MDNR tag in the side of:
8" Hemlock N70E 24.95' mrkd "S21 NBT"
18" Sugar S24E 9.85' "S28 NBT"
4" Sugar S72W 19.9' "S29 NBT"
14" Sugar N59W 41.0' "S20 NBT"
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(15) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
10" Hemlock N75E 9.3' mrkd "1/16S BT"
14" Hemlock S67E 8.0' do
9" Oak S28W 44.5' do
18" Hemlock N47W 35.4' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 07/10/2012

For the Michigan Department of Natural Resources, Forest Resources Division

