

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

or corners in

Menominee	Located In:	Corner Code #
(County)		
Public Land Survey	T 37N R 25W	K04
	T 37N R 25W	L05
	T	
Property Controlling Section	S T R	
	S T R	
	S T R	
Miscellaneous Property in Sec.	S T R	
	S T R	

1. Lot No. , Recorded Plat
2. Private Claims

8/15/2013AD
Jeremy J. Pipp, in a field survey on 9/10/2013AD do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

(K04) Quarter corner common to Sections 11 and 12. 1853: George Adair, DS. Set quarter
section post witnessed by Cedar 8 N53E 7 links (4.62'), Cedar 10 S74W 10 links (6.60').
1968: Michigan DNR (Frank Bray PS#13575) Set 1" pipe with 4" Aluminum cap witnessed by
3" Cedar N34E 20 1/2 links (13.53'), 8" Cedar S10E 22 links (14.52').

(L05) Quarter corner common to Sections 12 and 13. 1853: George Adair, DS. Set quarter
section post witnessed by Tamarack 8 N76E 30 links (19.80'), Spruce 6 S88W 45 links
(29.70'). No evidence of subsequent establishment.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K04) Accepted found MDNR Monument and two existing NBT Witnesses. Position is accepted
as a careful and faithful REESTABLISHMENT of the position of the original corner.

(L05) No evidence of original survey. Corner position reestablished by single
proportionate measurement between the Southwest corner and the Southeast corner of
Section 12. Position is accepted as a careful and faithful REESTABLISHMENT of the
position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K04) DNR monument
EX 6" Cedar N41E 13.39' (1/4S,NBT)
EX 10" Cedar S07E 16.09' (1/4S,NBT)
5" Tamarack N86W 30.23' (1/4S,NBT)
5" Tamarack N52W 20.70' (1/4S,NBT)
All trees are blazed, scribed, painted,
and signed. Measurements are to nail in
side of tree, bearings are magnetic. A
Metal rail was set North 1.15 feet.

Signed by
Surveyor's Michigan License No. 50447

(L05) DNR monument
10" Cedar N01E 6.50' (1/4S,NBT)
4" Cedar S72E 4.97' (1/4S,NBT)
5" Cedar S04E 18.03' (1/4S,NBT)
5" Cedar S46W 5.28' (1/4S,NBT)
All trees are blazed, scribed, painted,
and signed. Measurements are to nail in
side of tree, bearings are magnetic. A
Metal rail was set North 1.5 feet.

Date October 1, 2013

For the Michigan Department of Natural Resources, For the Michigan State Board of Professional Surveyors

20274

20275

