

P.A. of 1990 On 9/25, 19996
McAmis RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

1. Public Land Survey

T37N R 25W

A02

T R

T R

T R

T R

2. Property Controlling
In Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

RECEIVED FOR RECORD
96 OCT -7 PM 3 26
CASE # 362 BK 4
CAROL ANN MORRISON
REGISTER OF DEEDS
MENOMINEE COUNTY
RECEIVED 10/1/96

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SAME AS CORNER M-02 T37N-R26W

I, William Lenca, in a field survey on May 15, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1847: Original Survey by James H. Mullett - B.T.'s - Hemlock, 5" - N54°W - 32 lks; Sugar Maple, 8" - S54°W - 25 lks. All original evidence has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Finding no original evidence, subsequent restorations or occupational evidence, we re-established this corner on a straight line and proportionately between the Northwest Corner of Section 6 (A-1) and the Southwest Corner of Section 6 (A-3). The corner thus monumented falls 4 feet West of the centerline of a North - South County Road, and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum. cap stamped for corner location:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"
7" dia. Cedar
7" dia. Maple
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"
Metal Survey Sign Post

N45°E 44.65 feet 1' W. of 2" Cedar
S39°E 72.09 feet Scr. NBT
S42°W 50.24 feet Scr. NBT
West 27.14 feet
West 27.6 feet



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Sep. 24, 1996