

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Menominee Located In: Corner Code #
1. Public Land Survey T 40N R 25W C11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Table with 13 rows and 13 columns (A-M) for recording deed stamps and file numbers.

3/12/2014
Jeremy J. Pipp, in a field survey on 6/03/2014 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

(C11) Section corner common to Sections 29, 30, 31, and 32. 1852: Harvey Mellen, DS. Set section
corner post witnessed by Cedar 6 S24W 24 links (15.84'), Tamarack 9 N58E 17 links (11.22'). 1971:
Michigan DNR (Frank Bray PS#13575) Set 1" pipe with 4" Aluminum cap from original BT's NE & SW
witnessed by 10" Cedar N50E 10.7', 6" Cedar S40W 10.7'.

(D09) Quarter corner common to Sections 20 and 29. 1852: Harvey Mellen, DS. Hemlock 24 Quarter
section corner witnessed by Sugar 10 S38E 29 links (19.14'), Hemlock 14 N85W 33 links (21.78'). No
evidence of subsequent establishment.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C11) Accepted found MDNR Monument and Two existing NBT's as a careful and faithful PERPETUATION of
the position of the original corner.

(D09) No evidence of original survey. Corner position reestablished by single proportionate
measurement between the Northeast corner and the Northwest corner of Section 29. Position is
accepted as a careful and faithful REESTABLISHMENT of the position of the original corner. Location
is +/- 7 feet South of East-West Road and +/-40 feet East of NE-SW access driveway. (NOTE: No trees
available in NE,SE, & SW Quadrants)

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C11) DNR monument (D09) DNR monument
EX 11" Cedar N52E 11.00' (S 29,NBT) 8" Maple N32W 82.16' (1/4S,NBT)
5" Cedar S57E 18.55' (S 32,NBT) 5" Maple N47W 50.58' (1/4S,NBT)
EX 6" Cedar S43W 10.78' (S 31,NBT) 5" Maple N57W 68.71' (1/4S,NBT)
5" Cedar N61W 20.15' (S 30,NBT) 15" Basswood N66W 89.73' (1/4S,NBT)
All trees are blazed, scribed, painted, and signed. Measurements are to nail in
side of tree, bearings are magnetic. A Metal sign post was set North 1.5 feet.
Signed by [Signature] Date July 9, 2014

Surveyor's Michigan License No. 50447

For the Michigan Department of Natural Resources, Forest Resources Division

