

FEB 06 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY SECTION  
(County)

Located In:

Corner Code ##

ALBERT TWP.

- 1. Public Land Survey T 29N R 1E
- 2. Property Controlling S T R
- 3. Miscellaneous S T R

M.P.# 10

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed

12-16-1997 10:53:23

A. PANGAN-MCELROY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, DONALD E MARLATT in a field survey on 6/11, 19 97 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M.P.# 10 M.P. COMMON TO SEC.'S 27 & 28. ON NORTH SHORE OF EAST TWIN LAKE, GLO CORNER SET LEWIS CLASON APRIL 1840. W.PINE 12"-N50°W-21 L., ASPEN 8"-N26°E-32 L. F.SMITH NOTES-STEVEN'S FD. GAS PIPE 8/3/39. NBT Y.PINE 14" S40°W 1.5', B.OAK 10" S88°E 39.2'. F. SMITH SURVEY SEPT. 1947. S. THORSEN SURVEY JUNE 30, 1954. S. THORSEN SURVEY FOUND 1"PIPE. 7/12/1955. N.C. CALDWELL SURVEY 9/4/1970. R.S.SCOTT ENG. CO. INC. 1/21/74.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M.P. # 10 M.P. COMMON TO SEC.'S 27 & 28 ON NORTH SHORE OF EAST TWIN LAKE FD. 1/2"ROD & CAP#12018 AND 1"PIPE ALONG SIDE.

VERIFIED POSITION WITH S. THORSEN SURVEY DATED 7/12/55.


APPROVED BY  
PEER GROUP

JUL 11 97

*L.A.B*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M.P. # 10 M.P. COMMON TO SEC.'S 27 & 28 ON NORTH SHORE OF EAST TWIN LAKE. SET CONC. MONUMENT WITH REMON. CAP. S81°W 28"OAK 29.15' S73°E 28"WILLOW 55.35' N55°E 21"W.PINE 76.63' N20°W TWIN 12"MAPLE 74.54'



WITNESSES MARKED WITH 40PENNY SPIKES AND P.S. TAGS # 18660. APPROVED BY PEER GROUP JULY 11, 1997 AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Donald E Marlatt*

Date *12/15/1997*

Surveyor's Michigan License No. 18660