

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MONTMORENCY
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 31N R 3E

I-1

T R

I-2

T R

I-3

T R

I-4

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, CARL R. JOHNSON, in a field survey on JANUARY 7, 19 92,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1

I-2

I-3

I-4

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1

SET AT FOUND OLD SQUARED POST
NEAR RECORD DISTANCE WEST OF A
FOUND 1/2" PIPE FOR STANDARD
CORNER OF SECTIONS 34&35,
T32N,R3E

I-2


SET BY SINGLE PROPORTIONATE
MEASUREMENT BETWEEN SECTION
CORNER SOUTH AND CLOSING
CORNER NORTH.

I-3

SET BY SINGLE PROPORTIONATE
MEASUREMENT BETWEEN SECTION
CORNERS 1 MILE SOUTH AND
CLOSING CORNER TO NORTH.

I-4

SET MIDWAY AND ON LINE BETWEEN
SECTION CORNERS.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1

NE CORNER SEC. 3
DNR MON.

I-2

E1/4 COR. SEC. 3
DNR MON.

I-3

NE COR. SEC. 10
1/2" BAR W/CAP

I-4

E1/4 COR. SEC. 10
DNR MON.

SPRUCE 6" N09W 13.8 FT.
CEDAR 4" S48E 28.1 FT.
SPRUCE 8" N81E 28.1 FT.
SPRUCE 4" S16W 13.4 FT.
1/2" PIPE S84E 68.8 FT.

TRIPLE OAK 6" N14E 20.4 FT.
N.PINE 14" S48W 42.4 FT.
N.PINE 10" S03E 63.5 FT.
N.PINE 8" S63E 63.8 FT.
CEDAR POST N07RH 15.0 FT.

N.PINE 8" N27E 50.0 FT.
J.PINE 8" N21W 51.9 FT.
N.PINE 8" S52W 63.1 FT.
N.PINE 6" S48E 69.0 FT.
TRAIL RD. N-S 12 FT. EAST.
3.5 FT. SOUTH OF CENTERLINE
OF BLACKTOP E-W.

N.PINE 20" S67E 43.2 FT.
R.PINE 6" N70E 50.5 FT.
MAPLE 10" N13E 47.4 FT.
MAPLE 6" S46W 19.4 FT.
APPROX. 20 FT. EAST TO N-S
FIREBREAK TRAIL.

Signed by

Carl R. Johnson

Date

3/17/92

Surveyor's Michigan License No.

30083