


# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Montmorency</u> (County)	Located In Hillman (Township)	Corner Code #
1. Public Land Survey	T 31N R 3E	K-7
2. Property Controlling in Section	S _____	_____
3. Miscellaneous Property in Section	S T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number



I, Carl T. Kiiskila, in a field survey on January 26, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

K-7 GLO-1850 Hiram Burnham set Cedar post for corner to sections 13, 14, 23 & 24.  
 Witnesses: Lynn 14" N89°W 11 Links  
 Ironwood 10" S55°E 5 Links

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

K-7 Re-established the section corner common to sections 13, 14, 23 & 24 by double proportionate measurement between found corners one mile to the East, one half mile to the North and South and two miles to the West. Accepted as careful and faithful re-establishment of the position of the corner by peer group 8-05-05.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-7 Set 1" X 32" pipe with standard DNR cap.

- Wit: 6" Basswood N07°E 14.29'
- 8" Balsam S20°W 4.45'
- 12" Maple N29°W 25.55'
- 6" Spruce N78°E 35.44'
- ½" Iron N02°E 290.49'
- N-S Barbwire fence (down) West 2'±
- Blue Carsonite Post North 1'±
- Placed 60 d spikes in trees (typ.)



Signed by: Carl T Kiiskila  
 Surveyor's Michigan License No.: 33981

Date: 2-1-06