


**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Montmorency (County)	Located In Vienna Twp.	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>24</u> T <u>32N</u> R <u>3E</u>	<u>3</u>
	S <u>24</u> T <u>32N</u> R <u>3E</u>	<u>5</u>
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		



I, Carl T. Kiiskila, in a field survey on February 17 2010 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

3 - N 1/16 Corner comm. to sec.'s 23&34, T32N,R3E

5 - CN 1/16 Corner, Section 24, T32N,R3E

Survey, unrecorded - Donald E. Marlatt,  
P.S.#18660 - Set 1/2" rod and cap.

Cert. of Survey, unrecorded - Donald E. Marlatt,  
P.S.#18660 - Set 1/2" rod and cap.

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

3 - N 1/16 Corner comm. to sec.'s 23&34, T32N,R3E

5 - CN 1/16 Corner, Section 24, T32N,R3E

Found 1/2"CIR#18660 per unrecorded survey by Marlatt. E-W single strand fence running 16.5' South of corner. Found no other evidence to dispute the location of the corner. Accepted found 1/2" CIR as the best available evidence for the position of the corner.

Found 1/2"CIR#18660 per unrecorded survey by Marlatt. Corner falls 21' South of a fence post corner w/single strand wire running West and South. Found no other evidence to dispute the location of the corner. Accepted found 1/2" CIR as the best available evidence for the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

3 - N 1/16 Corner comm. to sec.'s 23&34, T32N,R3E

5 - CN 1/16 Corner, Section 24, T32N,R3E

Found 1/2"CIR#18660.

Found 1/2"CIR#18660.

Wit: \*S22°E 8.44' to fd. nail on NW side 15" R. Oak  
\*S07°W 27.75' to fd. nail on E side 10" R. Oak  
\*N85°W 19.64' to fd. nail on N side 12" R. Oak  
\*N33°W 3.91' to fd. nail on SW side 4" Maple  
Set Blue Carsonite post w/location tag 2' North.

Wit: N41°E 47.92' to set N&T on NW side 12" B. Fir  
\*S87°E 5.96' to fd. nail on S side 6" R. Maple  
\*S25°W 23.94' to set N&T on W side 4" B. Fir  
\*N34°W 8.81' to fd. nail on S side 6" R. Maple  
\*N09°E 13.59' to fd. nail on W side 5" Poplar  
Set Blue Carsonite post w/location tag 1' North.

\* Previous recorded witness.

\* Previous recorded witness. 3-25-10

Carl T. Kiiskila

Surveyor's Michigan License No.: 33981

