

NOV 17 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda

(County)

Located In:

Corner Code #

1. Public Land Survey

T 26N R 2E

A - 2

T R

T R

T R

T R

2. Property Controlling

S T R

in Section

S T R

3. Miscellaneous

S T R

Property in Section

S T R

4. Lot No. , Recorded Plat

5. Private Claims

STATE OF MICHIGAN
OSCODA COUNTY

FILED

2 AUG 95 9:34 A.M.

PATSY J. PETERS
Register of Deeds Stamp & File Number
REGISTER OF DEEDS

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 |
| 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 |
| 27 | 28 | 29 | 30 | 31 | 32 | 33 | 34 | 35 | 36 | 37 | 38 | 39 |
| 40 | 41 | 42 | 43 | 44 | 45 | 46 | 47 | 48 | 49 | 50 | 51 | 52 |
| 53 | 54 | 55 | 56 | 57 | 58 | 59 | 60 | 61 | 62 | 63 | 64 | 65 |
| 66 | 67 | 68 | 69 | 70 | 71 | 72 | 73 | 74 | 75 | 76 | 77 | 78 |
| 79 | 80 | 81 | 82 | 83 | 84 | 85 | 86 | 87 | 88 | 89 | 90 | 91 |
| 92 | 93 | 94 | 95 | 96 | 97 | 98 | 99 | 100 | 101 | 102 | 103 | 104 |
| 105 | 106 | 107 | 108 | 109 | 110 | 111 | 112 | 113 | 114 | 115 | 116 | 117 |
| 118 | 119 | 120 | 121 | 122 | 123 | 124 | 125 | 126 | 127 | 128 | 129 | 130 |

I, Marvin E. Myers, in a field survey on May 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-L. Clason May 1839

Mon-Post

WIT: 16" Y.Pine

12" Spruce

Swamp South 2.6 chs.

Fargo Engineering 1908-1909

Mon-Fd. stake

WIT: 12" Spruce N68½°E 16 lks.

8" Spruce N16½°W 26 lks.

G.F. Delamatter Feb. 25, 1924

Mon-Fd. post

WIT: 30" W.Pine S04°E 13½ lks.

6" Fir S27°W 36 lks.

12" S.Pine N68°E 16 lks.

8" S.Pine N66°W 26 lks.

GLO-G. Veal Oct. 1935

Mon-Fd. 1" pipe set by Fargo

Replaced pipe with Conc.

Mon. & Brass Cap

WIT: 7" J.Pine N37°E 85½ lks.

8" J.Pine N86°W 52½ lks.

G.D. Henning May 7, 1941

Mon-US GLO

WIT: None given

L. pg.222 L.G. Beauregard April 18, 1979

Mon-Set ½"x24" Bar & Cap from GLO witness

dependent re-survey 1935

WIT: 12" J.Pine N37°E 56.43'

8" J.Pine N86°W 34.65'

8" J.Pine N65°W 17.40'

L.3, pg.425 Ed. J. McCombs May 10, 1984

Mon-Fd. Rebar & Cap

WIT: dead Spruce N55°W 12.53'

dead Spruce N80°W 35.00'

Pine N40°E 56.80'

10" Pine S54°E 52.79'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" Bar & Cap in North track of trail road

Found still stand US GLO 8" J.Pine (with scribing on face) N80°W 34.65'

Found 15" J.Pine

And is accepted as a perpetuation of the original government corner.

APPROVED

County Remonumentation

Peer Review Group

NCC/31 406 9.5
JULY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Mon-Set 5/8" X 30" Bar with Standard County Cap

WIT: Set nail SW face 8" J.Pine N54°W 22.06'

Fd. 15" J.Pine N93°E (recorded as N87°E) 56.43'

Set nail SE face 15" B.Oak N35°E 76.58'

Set nail side Red Top USFS location post East 33.21'



Signed by

Marvin E. Myers

Date

July 29, 1995

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983