

SURVEY & REMONUMENTATION

DEC 01 1993

OTTAWA COUNTY REMONUMENTATION

RECORDED

93 NOV 11 AM 11:53

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **OTTAWA**

(County)

Located In:

Corner Code #

1. Public Land Survey

T 6N R 13W

G-7 (NE cor

T R

Section 21)

T R

Georgetown Twp

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

I, Randal J. Vugteveen, in a field survey on July 16, 19 93,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G-7 Corner common to Sections 15, 16, 21 & 22, Georgetown Township

LCRC Liber 1, Page 631

LCRC Liber 3, Page 33

Conc. Monument

PK Nail

Ash clump NE 7.17'

Top of steel fence post S0E 33.33' / NE

16" Ash S 17.35'

cor of garage (Taylor St.) S15W 82.57' /

Nail in Pymt W-NW 39.32'

Nail & cap in Twin Hickory NOE 43.82'

Conc. Mon. N 33.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7 Found PK nail on centerline Tyler between Coconut & Roselane and accepted as a careful and faithful perpetuation of the position of the original corner

1/4" rod in conc. mon N 33.35'

Top of steel fence post S0E 33.35' / NE

cor of garage (Taylor St.) S15W 82.57' /

Nail in Twin 14" Cherry tree NOE 43.78'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


G-7 Set Ottawa County Remon Tag & Nail cap on 24" X 3/4" solid iron

NE brick corner garage hse #2406 S15W 82.57'

Set Ottawa County Remon Tag & Nail in Twin 14" Cherry NOE 43.78'

NW corner brick hse #2406 S45W 111.25'

Set Ottawa County Remon Tag & Nail in S side 12" Maple N65W 93.42'



Signed by

Randal J. Vugteveen

Date

Nov 5, 1993

Surveyor's Michigan License No.

28429

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983