

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON

(County)

Located In:

Corner Code #

1. Public Land Survey

T48NR 41W

J-7

T R

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

SURVEY
FILED

JAN 11 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 14 & 23, T48N R41W.

I, Earl W. Applekamp, in a field survey on August 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 19, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

40" White Pine S77°W 10.56 feet
10" Spruce N54°E 7.92 feet

FREE GROUP APPROVAL

Earl W. Applekamp
COUNTY REPRESENTATIVE 8-19-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. A fence was running North, South and West from the apparent corner. The corner post of the fence running West was large and has been there for an estimated 60 years. The calculated position of the corner falls 11 feet South of the fence going West. I re-established the corner at the intersection of the North-South and West fence line.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 $\frac{1}{2}$ "X30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R41W, $\frac{1}{4}$, S14, S23, 1998, P.S. 17610. I established three bearing trees and a reference object

Nail in 6" Aspen S22°W 31.77' - Nail in 6" Aspen S53°E 42.44'

Nail in 4 $\frac{1}{2}$ " Aspen N59°W 24.15' - 6' Steel Sign Post North 0.77'

Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date August 14, 1998

