

SURVEY &
REMONUMENTATION

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon

(County)

Located in:

Corner Code #

1. Public Land Survey T 48N R 42W
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

E-F-11

Other

#3 pm

Recorded December 7 1994
at 4:15 o'clock P.M. in

Liber 3 page 233

Julie M. Ashley dep't
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

Meander corner common to Sections 28 and 33, T48N, R42W.

I, John R. Garske, in a field survey on November 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Survey by Austin Burt, August 1848. Set a W. birch post from which a 8" aspen bears S84°E, 65 links and a 24" W. pine - N64°E, 18 links.

Survey by John R. Garske, September 1991. Found a 1 3/4" O.D. iron pipe - 8" hemlock - S79°E, 16.35 feet; 7" cedar - S35°E, 23.52 feet; 10" cedar - S20°W, 8.65 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence could be found due to logging activity and developmental construction. I found a 1 3/4" iron pipe as noted above which has been used in many surveys and is generally accepted as the meander corner and is the only possible corner position due to all the development referenced to it.

Corner record research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I updated the corner position to state and county specifications by placing a brass cap on top of iron pipe, stamped to indicate corner position. I established the following bearing trees and reference objects: 8" hemlock - S79°E, 16.35 feet; 7" cedar - S35°E, 23.52 feet; 10" cedar - S20°W, 8.65 feet; edge of water - 12.0 feet; 6 foot steel rail with sign.


Signed by

John R. Garske

Date

11/28/94

Surveyor's Michigan License No. 28410



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

FED. No. V-9-10

233