

**SURVEY &
REMONUMENTATION**

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ontonagon

(County)

Located In:

Corner Code ##

1. Public Land Survey Section 20T 48N R 42W
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

D-E-9

#006

Recorded August 31 19 94
at 2:05 o'clock P. M. in
Liber 3 page 207
Julia M. Kirby Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John R. Garske, in a field survey on May 2, 19 94,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, U.S.D.S., on August 2-12, 1848. Set cedar post. Original
Bearing Trees: 9" hemlock - S79°E - 34 links; 8" cedar - N25°W - 9 links

Survey by E.W. Applekamp, RLS 17610, in 1983 and 1985. Corner position is marked by a
1/2" iron pin.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1/2" iron pin marking the corner position as described above. I accepted this position as
being true due to its use in many surveys of record and the corner's longevity. I remonumented
corner position and updated the accessories to state and county specifications as noted below.

Research on file with County Remonumentation Program Representative.

ONTONAGON COUNTY

PEER APPROVED

Earl Applekamp Co. Rep.
8-17-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1/2" iron pin with a 3/4" x 30" rebar with a 3 1/4" aluminum cap stamped: County
Monumentation, M.C., S-20, S-29, T48N, R42W, 1994, RLS 28410. I established the
following bearing trees and reference objects:

Steel sign post - S15°W - 1.44 feet
8" spruce - S52°E - 10.24 feet
4" ash - N85°E - 3.69 feet
10" spruce - N18°W - 15.51 feet

Signed by


John R. Garske

Date

6/8/94

Surveyor's Michigan License No.

28410



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983