

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Form with fields for Ontonagon (County), Located In, Corner Code #, and sections for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Register of Deeds Stamp & File Number

Table with 13 rows and 13 columns (A-M) for recording deed stamps and file numbers.

I, Stephan J. Szyszkoski, in a field survey on 08/12/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F4) Center of Section 9. 1976 - Established by K.L.Sackett RLS. Set 1"IDx36" I.pipe with 4" aluminum cap. 7" Sugar N11°E 16.7'; 7" Sugar S06°E 8.4'; Squared marker tree 5" Sugar N42°W 2.4'.

(5-Sec. 3) Center-North 1/16 corner, Section 3. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F4) The 1976 monument was not found and it appears that it has been removed by logging equipment. Reestablished the position for the corner at the intersection of straight lines connecting opposite 1/4 corner of Section 9, which position also falls at record bearing and distance from the two 1976 BTS: The Sugar NE is in good condition, the Sugar SE is a cut stump with lower blaze visible. The 1976 marker tree has been disturbed by heavy equipment.

(5-Sec. 3) Established the position for the corner on a straight line between Center of Section 1322.94' south and Quarter corner H1 1335.18' north, both proportionate to the original record which is 20 chains north of the Center of Section 3 and 40.185 chains south of H1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F4) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 10" Sugar N13°E 16.85' old blazes (1976 BT) 8" Sugar S22°W 15.3' mrkd "C1/4 BT" 7" Sugar S78°W 17.0' do 4" Sugar N30°W 20.75' do Set sq'd cedar post adjacent. E= 7846978.379 N= 229378.686

(5) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 14" B.Ash N06°E 24.4' mrkd "1/16S BT" 9" B.Ash S75°E 14.5' do 10" B.Ash S09°W 6.65' do 8" Sugar N56°W 33.4' do Set sq'd ash post adjacent. E= 7848623.628 N= 231377.518

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum. Coord. Ref.=NGS PID RL0593: N= 221669.506 m. E= 7868965.488 m.

Signed by [Signature] Surveyor's Michigan License No. 33986

Date 08/26/2015

For the Michigan Department of Natural Resources, Forest Resources Division

