

# LAND CORNER RECORDATION CERTIFICATE

## Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON

(County)

Located In:

Corner Code #

## 1. Public Land Survey

T 51NR 41W

A-11

T 51NR 42W

M-11

T R

T R

2. Property Controlling  
in Section

S

T R

S

T R

3. Miscellaneous  
Property in Sec.

S

T R

S

T R

SURVEY  
PEARSON

JAN 21 1998

SECTION

Register of Deeds Stamp &amp; File Number

## 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

## 5. Private Claims \_\_\_\_\_

Section Corner common to Sections 30 & 31, T51N R41W  
& Sections 25 & 36, T51N R42W.

I, Earl W. Applekamp, in a field survey on March 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

## A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, September 1845. Set Wood Post.

## ORIGINAL BEARING TREES:

16" Birch S15°W 10.56 feet  
14" Birch N72°W 17.82 feet

PEER GROUP APPROVED

Earl W. Applekamp  
COUNTY REGISTER  
5-13-98

## B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Extensive logging has taken place several times, most recently it had been clear-cut. At the calculated position I found a 1"x34" bolt in the ground about 2 feet Northerly and a decayed cedar post lying next to it. Copper Range cruisers did some work in this area in the 1940's. No documentation could be found. I accepted the bolt location as it was in conformance with feature calls East & West and distance & bearing to opposite corners North & South.

Research on file with the Ontonagon County Remonumentation Program Representative.

## C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2½"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T51N, R41W, R42W, S25, S36, S30, S31, 1998, P.S. 17610. I established 3 bearing trees and one reference object.

Nail in 7" Y. Birch, S23°W, 13.86' - Nail in 8" Y. Birch, S28°E, 40.89'  
Nail in 7" Maple, N76°W, 35.12' - 6' Steel Sign Post, North, 0.81'



Signed by Earl W. Applekamp  
Surveyor's Michigan License No. 17610

Date March 26, 1998