

APR 29 1996

COMMISSION

JUDITH D. ROEHM 10/19/95
Ontonagon County 14:17
LC 3/343 JEM Fee: 9.00
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ontonagon Located in: Corner Code #
(County)

- | | | | | | |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey | T | 52N | R | 39W | F-13 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | R |
| | S | | T | | R |
| 3. Miscellaneous | S | | T | | R |
| Property in Section | S | | T | | R |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, Joseph C. Domitrovich, in a field survey on October 5, 19 95
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

South 1/4 Corner Section 33, T52N, R39W

1845 - William A. Burt set 1/4 section post
14" Hemlock N 67° E 22 links
9" Sugar N 64° W 9 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

All evidence of original corner has been obliterated by extensive farming. An old East-West fenceline falls of the North side of a cleared field. A newer fenceline falls just to the south of it.

Corner position was re-established midway between standard section corners, and the older fence was used to establish the North-South position.

(Research on file with County Remonumentation Representative.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Corner is an aluminum pipe with 3" diameter stamped aluminum cap and falls on an old East-West fenceline at the North side of a field.

Witnesses:

6" poplar	N 30° W	7.18'
12" Red Pine	N 23° E	23.71'
30" Soft Maple	N 80° E	24.30'
North 1/4 Corner Section 4, T51N, R39W (Stamped Monument)	East	52.80'
Sign Post	South	0.45'

PEER GROUP APPROVED

COUNTY REPRESENTATIVE



NOTE: -- Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich

Date 10/18/95

Surveyor's Michigan License No. 37273

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983