

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Ontonagon (County)	Located In:	Corner Code #
1. Public Land Survey	T 53N R 37W	H7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 15 T 53N R 37W	H6
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

I, Stephan J. Szyszkoski, in a field survey on H7 07/26/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H7) Quarter corner common to Sections 15 & 22. 1846 - Established by S.W.Higgins, Deputy Surveyor,
on the Section line between Section corners 40.03 chains east and 40.04 chains west. Set post.
Sugar 12" S30E 2 links, Y.Birch 12" N5E 34 links. 1988 - R.A.Mick LS #16936, on a drawing of a
survey titled "Misery Bay Recreational Lots", implies that the corner is located S00 deg. 26' 07"W
2661.50' from the Center of Section 15 (Bearings from solar observation but location of observation
is not stated). No monument or witnesses specified.

(H6) Center of Section 15. 1988 - Established by R.A.Mick RLS #16936 at the intersection of straight
lines connecting opposite 1/4 corners.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H7) Found a 2"ID aluminum pipe monument with a 3 1/4" magnetized aluminum cap stamped to identify
the corner by R.A.Mick LS #16936, dated 1988. Observed true bearing and distance to Center of
Section 15 is N 00 deg. 27' 33"E 2661.32'. Distance west to G7 is 2648.78', which agrees closely
with the original record. Two nearby trees appear to have long ago been marked as witnesses, for
which I have no record: a Sugar N75W 2.6' to center, now dead and broken, and a Hemlock, described
below. I accepted the monument as the best available evidence of the position of the original
corner.

(H6) No monumentation was recovered at the corner position. Remonumented the corner at the
intersection of straight lines connecting opposite Quarter corners. Observed bearings and distances
to Quarter corners N-S-E-W agree very closely with those shown on R.A.Mick's survey drawing for
"Misery Bay Recreational Lots", dated 1988.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H7) Fd. 2"ID alum. pipe with 3.25" alum cap.
Set measuring nail with MDNR tag in the side of:
21" Hemlock N19E 15.0' mrkd "1/4S NT"
12" Sugar N64E 27.6' do
4" Y.Birch S87E 12.95' do
4" Y.Birch N85W 75.25' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(H6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
7" Maple N56E 28.9' mrkd "C1/4 BT"
7" Sugar S38E 32.05' do
7" Sugar South 27.95' do
9" Sugar N14W 34.6' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11/29/2012

For the Michigan Department of Natural Resources, Forest Resources Division



16951

16950