

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Ontonagon (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 16 T 53N R 37W	8
	S 21 T 53N R 37W	5
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 8 08/23/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(8-Sec. 16) West 1/16 corner, Section 16. 1979 - Established by K.L.Sackett RLS midway and on a
straight line between Quarter corner E6 and Center of Section F6. Set snow fence "T" iron in beaver
pond. 10" Maple N04E 43.0', 6" Maple S52E 68.3', 9" Maple N70W 70.9'.

(5-Sec. 21) North 1/16 corner, Section 21. 2006 - Established and monumented by Todd G. Maki PS
#49300.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 16) The 1979 subdivision of Section 16 by Mr. Sackett was shown to be erroneous by Todd G.
Maki PS #49300 in 2006 and was partially corrected by him in that year. This 1979 corner position
also suffers from the error. I reestablished the position for this corner midway and on a straight
line between Quarter corner E6 1359.04' west and Mr. Maki's Center of Section at F6 1359.04' east.

(5-Sec. 21) Found a 5/8" rebar with plastic cap stamped "Maki PS 49300", projecting 14" a.g., in good
condition and substantially at the position midway and on a straight line between corners F7 and F8.
Accepted same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
11" Maple N64W 60.9' old blazes 1979 BT
13" Maple N24E 45.6' do do
9" Maple S53E 77.25' do do
11" Maple S19E 88.8' mrkd "1/16S BT"
Set sq'd cedar post adjacent.
Bearings are magnetic.

(5) Found 5/8" capped rebar #49300
Set measuring nail with MDNR tag in the side of:
9" Sugar N36W 5.15' mrkd "1/16S BT"
7" Y.Birch N09E 28.9' do
8" Maple S86E 10.85' do
6" Sugar S09W 5.0' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11/29/2012

For the Michigan Department of Natural Resources, Forest Resources Division

