

1999 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

DEC 29 1999

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Presque Isle  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 34 R 4 E

B-1

T R

T R

T R

T R

2. Property Controlling  
in Section

S

T R

S

T R

3. Miscellaneous  
Property in Sec.

S

T R

S

T R

4. Lot No. , Recorded Plat

5. Private Claims

PRESQUE ISLE COUNTY  
RECORDED

1999 DEC -2 PM 2:13

Jesse M. Lamb  
REGISTER OF DEEDS

Register of Deeds Stamp &amp; File Number

I, Delmer E. Porter in a field survey on Nov. 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													


## A. Description of original monument and accessories and/or subsequent restoration:

B-1 GLO Notes - 1840  
Set Quarter Section Post  
6" Spruce Pine N45°W 18 Lks  
6" Spruce Pine N7°E 13 Lks

K. Ostling #10068  
Set DNR Monument by  
Proportionate Measurement  
6" R. Pine S03°W 77.3'  
8" J. Pine S52°W 45.9'

## B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 Found DNR Monument and Ostling's  
2 Witnesses in Place



## C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 DNR Monument  
S03°W 77.3' 14" R. Pine  
S52°W 45.9' 13" J. Pine  
N48°W 43.21' 14" J. Pine  
S81°E 48.83' 7" J. Pine

\*Witness tags & nails used.

Reaffirmed by Peer Group  
in accordance with P.A. 345

Chairman Norman J. O'Leary  
Date 11/30/99

Signed by

Date

11-15-99

Surveyor's Michigan License No. #15410