

FILED

1993

PRESQUE ISLE COUNTY
RECORDED

93 DEC 22 AM 10:00

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

PRESQUE ISLE
(County)

Located In:

Corner Code #

Janet M. Lamb
REGISTER OF DEEDS

- | | | |
|------------------------------------|---|-------------|
| 1. Public Land Survey | T <u>34N</u> R <u>2E</u> | <u>A-10</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, DELMER E. PORTER field survey on DEC. 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-10 GLO SURVEY
June 2, 1840
LYNN 4" S 47° W 3 lks.
BIRCH 12" N 50° W 37lks.

A-10 Dec. 8, 1977 P.A. 74
FILING RONALD R. BISCHER
Pg. 209, LAND CORNER RECORDS
SET 1/2" ROD & CAP 15410
AT FENCE CORNER

WITNESSES

N 82° W 33.88' 6" MAPLE
S 41° E 19.45' 7" Y. BIRCH
N 38° E 4.66' 13" Y. BIRCH
A-10 Nov. 6, 1978 P.A. 74

FILING BY DELMER E. PORTER
LS 15410 PAGE 375 LAND CORNER
RECORDS, PRESQUE ISLE COUNTY
REMONUMENTATION MONUMENT

WITNESSES

SAME AS
DEC. 8, 1977
FILING.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


A-10
FOUND 4" CONCRETE MONUMENT WITH BRASS CAP
AND ALL WITNESSES THE YELLOW BIRCHES
WERE IN POOR CONDITION

Validated by Peer Group
in accordance with P.A. 345

Chairman *Delmer E. Porter*
Date December 17, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A -10
4" CONCRETE MONUMENT WITH BRASS CAP
S 14° E 34.18' 6" MAPLE
N 81° W 34.25' 8" MAPLE
S 38° W 31.80' 4" IRONWOOD
N 27° W 51.79' 6" MAPLE
* NAILS AND TAGS USED ON WITNESSES
PORTER'S SURVEY, P.C.



Signed by *Delmer E. Porter*

Date Dec 20, 1993

Surveyor's Michigan License No. 15410

CORNER HISTORY RESEARCH SHEET

A-10

T34N,R2E ALLIS TOWNSHIP-NORTH PART,
PRESQUE ISLE COUNTY, MICHIGAN.

ACTIVITY	MONUMENT & ACCESSORIES	COMMENTS
----------	------------------------	----------

GLO Survey
June 2, 1840

Lynn 4" S47°W 3 Links
Birch 12" N50°W 37 Links

Act 74 filing by:
Ronald R. Bischer
#22428, Dec.8, 1977
Page 209, Corner
Recordation

Set 1/2" Rod & Cap #15410
at Fence Corner
N82°W 33.88' 6" Maple
S41°E 19.45' 7" Y. Birch
N38°E 4.66' 13" Y. Birch

Act 74 filing by:
Delmer E. Porter
#15410, Nov.6,1978
Page 375, Corner
Recordation

Fd. 1/2" Rod & Cap # 15410
N82°W 33.88' 6" Maple
N38°E 4.66' 13" Y. Birch
S41°E 19.45' 7" Y. Birch Project
Left P.I. Co. Remon. Conc. Mon.
with Brass Lap and Same Witnesses

Presque Isle
Remonumentation

Act 132 filing by:
Delmer E. Porter
#15410, June 4, 1986,
Survey#41-86, Recorded
File# 34R2190
Lib. Pg 267
293

Fd. Conc. Mon.
and above Witnesses

Shown on
Survey as
SW Corner of
Sec. 30, in
error

Mortgage Report
Porter's Survey
Apr.27, 1987
Survey#42-87
File#34R2190-M

Fd. Conc. Mon.
and above Witnesses

Shown on
Survey as
SW Coner of
Sec.30, in
error

Presque Isle
Remonumentation
Dec. 9, 1993

FD. 4" Conc. Mon. with brass cap
and all witnesses
Yellow birches in poor condition & replaced
S14°E 34.18' 6" Maple
N81°W 34.25' 8" Maple
S38°W 31.80' 4" Ironwood
N27°W 51.79' 6" Maple

Recording Data Does Not
Follow with Paper Train

CONVEY &
REMONUMENTATION

JAN 22 2001

SECTION

#31