

## SECTION

SAGINAW COUNTY REMONUMENTATION 1998  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIBER 2084 PAGE 841

Saginaw

(County)

Located In:  
Maple Grove Twp

Corner Code #

## 1. Public Land Survey

T 9 N R 4 E H-13

T R

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

## 3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

I, Ronald C. Prevost, in a field survey on 7-15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

## A. Description of original monument and accessories and/or subsequent restoration:

H-13 Post set by D.S. Joseph Wampler 1822±.  
Ash 7" S.63 1/2"E. 16 L.  
Elm 13" N.51"W. 15 L.  
P.K. nail & washer set by Rowe Eng. 1975 in line with fence to North.  
Act 132 L6, P933 Rauser #39096 1994.

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

*[Signature]* 8-5-98


## B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found P.K. nail & washer 0.1' below bit.  
Distance East to corner I-13 = 2631.00 (2631.11 R L6, P933).  
Distance West to corner G-13 = 2630.94 (2630.89 R L6, P933).

Accepted as the best available evidence of the position of the original corner.

## C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Replaced P.K. & washer with 5/8" bar, Saginaw Co. re-mon cap and mon box 9-16-98.  
S.14"W. 31.47 nail in wood post @ tel pedestal.  
S.07"W. 32.82 1/2" Re-bar w/broken cap.  
S.20"E. 51.12 face 12" Twin Maple.  
S.49"E. 84.15 face 10" Maple.



Signed by

*[Signature]*  
Ronald C. Prevost

Date

9-21-98

Surveyor's Michigan License No. 24612