

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

COMMISSION

| FOR CORNERS OF—:                                                           | LOCATED IN—: | CORNER CODE NUMBER |
|----------------------------------------------------------------------------|--------------|--------------------|
| 1. PUBLIC LAND SURVEY _____ T. <u>14</u> N. S., R. <u>4</u> E. W.          |              | <u>B-13</u>        |
| 2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.   |              |                    |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W. |              |                    |
| 4. LOT NO. _____, RECORDED PLAT _____                                      |              |                    |
| 5. PRIVATE CLAIMS _____                                                    |              |                    |

REC'D & FILED  
*Lib 6 Page 17 1/2*  
DEC 22 2 12 PM '93  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.  
REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Duane F. Ledy, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on September, 1993, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
Wood post set in 1822 by Wampler at 40.00 chains. No evidence of original monument or any subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
C-1 and B-1 for Township 11 North established for BIRCHVIEW PARK NO. 1 in 1961 and accepted as Standard line. B-13 set at proportional distances between A-13 and C-13 on line of B-1 to C-1 and accepted by Saginaw County Remonumentation Peer Group review on October 7, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rod & Sag. Co. Remon. 3" brass cap.

West 4.20 1" pipe; corner B-1 T11N, R4E

East 15.80 Concrete monument; NW corner Birchview Subdivision

N 45 E 88.81 Nail & brass tag marked "P.S. 21575" in S. side of 10" Ash

N 60 W 55.76 Nail & brass tag marked "P.S. 21575" in N. side of 20" Boxelder

S 30 E 20.77 Nail & brass tag marked "P.S. 21575" in W. side of 24" Elm

SIGNED BY

*Duane F. Ledy*

DATE

Dec. 22, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO.

21575

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY


DATE

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY

DATE

MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO.