

# SURVEY & REMONUMENTATION

SEP 17 1999

LIBER

2 PAGE 311

## 1999 REMONUMENTATION PROGRAM LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

99 AUG -2 AM 9:10

LIBER NO. 2 PAGE NO. 311  
MICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

SECTION

SANILAC

(County)

Located In:

Corner Code #

1. Public Land Survey

T12N R12E

A-9

T R

T R

T R

T R

2. Property Controlling  
in Section

S

T R

S

T R

3. Miscellaneous  
Property in Sec.

S

T R

S

T R

4. Lot No. , Recorded Plat

5. Private Claims

I, John A. Milletics, in a field survey on April 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

### A. Description of original monument and accessories and/or subsequent restoration:

- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S.-Set qr. Sec. post-Hemlock 8 S16W 25; Hemlock 6 N18½W 14
- 1983 (Survey for Ed M. Sowa-Sanilac Co.) John A. Milletics, P.S. 25859-shows Northwest Corner of Sec. 30, T12N-R12E-East 68.39' Set Iron Bar; East 93.54' Set Iron Bar (Note; Iron Bars set in North Section line as references to Section Corner)
- 1992 (Survey for John Powell-Tuscola Co., Sec. 25, T12N-R11E) Lionel Rop Emery, P.S. 24593 Found ½" Iron bars East of Drain as indicated on Milletics Survey-Found nothing at Sec. Corner-Set ½" Iron from reference irons, East, 68.39' ½" reinforcing rod with cap #25859 East 93.64' ½" reinforcing rod with cap #25859; S20°W, 33.03' nail in 14" Elm; N60°W 19.51' nail in 12" poplar

### B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 9

SW Corner Section 19 T12N-R12E

Found Standard Concrete Mounment with Brass Cap

South 2614.64 feet to the W 1/4 Corner Section 30

North 2621.25 feet to the W 1/4 Corner Section 19

Accepted as best evidence

APPROVED PEER BOARD MEETING

July 20, 1999

### C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Standard Concrete Monument with 2" Brass Cap  
East, 68.39' Found ½" reinforcing rod with cap #25859  
East 93.64' Found ½" reinforcing rod with cap #25859  
S20°W, 33.10' T.C. Re-mon. tag in East face of 16" Elm  
N82°W, 12.58' T.C. Re-mon. tag North face of post  
N60°W, 19.50' T.C. Re-mon. tag above found nail in East face of 18" poplar  
West, 10.0' "Survey Marker" witness post

Signed by

John A. Milletics

Date June 30, 1999

Surveyor's Michigan License No. 25859

