

ST. CLAIR COUNTY, MICHIGAN
OFFICIAL GOVERNMENT CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970



Located In: Kimball Twp. Corner Code #

1. Public Land Survey T 6N R 16E. A-3
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

RECEIVED
REGISTER OF DEEDS
ST. CLAIR COUNTY
1993 DEC 29 AM 9:00

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, John R. Lansky, in a field survey on Sept. 27-Oct 1, 1993
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 1 corner, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 20" Beech-- Original Gov't Survey.
- Nothing Listed on Old Surveyor's Rec.
St. Clair County for this corner
- Rod/with Disc. (Ref. Cert. L.3 P.416)
MSHD. (Ref. I-69 Plans)

STATE PLAIN COORDINATES

N. _____

E. _____

ELEVATION _____

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Rod with Disc.


2159A000 12/29/93MSSU4 9.00
0001
2159A000 12/29/93SSRE4 2.00
0001

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Rod with Disc. (At Fence line intersection Fence N,S,E.)

N'ly 7.30 ft. Set PK nail & tag in 18" Black Cherry
E'ly 24.30 ft. " " in 12" Ash
S'ly 17.55 ft. " " in 15" Oak

See attached sketch for additional information.



Signed by John R. Lansky
Surveyor's Michigan License No. 18659

Date October 6, 1993

PA 345-1990
PEER COMMITTEE

APPROVED 11-23-93

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

Signed By: _____
St. Clair County Land Surveyor

Date

Surveyor's Michigan License No. _____

LIBER 007 PAGE 128