

ST. CLAIR COUNTY, MICHIGAN  
OFFICIAL GOVERNMENT CORNER



LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Located In: Corner Code -#

Clyde Twp.

1. Public Land Survey T 7N R 16E E-13  
T R  
T R  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

4. Lot No. , Recorded Plat  
5. Private Claims

Register of Deeds Stamp & File Number

RECEIVED  
1995 AUG -4 AM 10:13  
REGISTER OF DEEDS  
ST. CLAIR COUNTY

I, Daniel E. Johnson May 26, 95  
in a field survey on 19  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

NOTE: Not more than 1 corner, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:

LIBER 007 PAGE 371

STATE PLAIN COORDINATES


N. \_\_\_\_\_

E. \_\_\_\_\_

ELEVATION \_\_\_\_\_

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

LIBER 007 PAGE 371



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2"x18" Rerod with 2" dia. aluminum cap inscribed "St. Clair County Official  
Corner" with magnet

in Monument Box on centerline of existing Lapeer Rd. pavement and  
centerline of McLain Rd to north. Located on the true Township line.

N 25°W 50.23' to set PK nail w/county remon tag in NE side of power pole  
N 22°E 70.08' to set PK nail w/county remon tag in W side of power pole  
S 24°W 52.06' to set PK nail w/county remon tag in W side of power pole  
S 40°E 90.41' to set PK nail w/county remon tag in NE side of twin 8" Box Elder  
WEST 2636.22' to S 1/4 corner of Section 32, T7N-R16E  
EAST 2636.56' to S 1/4 corner of Section 33, T7N-R16E

Signed by Daniel E. Johnson

Date May 26, 1995

Daniel E. Johnson

Surveyor's Michigan License No. #13754

PA 345-1990  
PEER COMMITTEE

APPROVED 6-10-95 Dave

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

Signed By: Daniel E. Johnson

St. Clair County Land Surveyor

Daniel E. Johnson

7-31-95

Date

Surveyor's Michigan License No. \_\_\_\_\_

#13754

LIBER 008 PAGE 84