

RECEIVED
COUNTY CLERK

MAY 20 PM 2:23

ST. CLAIR COUNTY
REGISTER OF DEEDS

ST. CLAIR COUNTY, MICHIGAN
OFFICIAL GOVERNMENT CORNER



LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Located In: Clyde Township Corner Code M-13

1. Public Land Survey T 7N R 16E T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, John C. Niederhauser, in a field survey on January 26, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 1 corner, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Wood post set by Joseph Wampler in 1822.
Referenced on Robbins Indian Village Subdivision--nothing recorded as to what corner is.
1/2" rerod listed in St. Clair County Road Commission topo notes of West Water St. book #739.

STATE PLAIN COORDINATES

N. _____

E. _____

ELEVATION _____

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found railroad spike on existing centerline of West Water St. pavement. Railroad spike is in line with fence to north. Verified location from previously recorded "Robbins Indian Village Subdivision" Plat, Liber 57, page 6 and from St. Clair County Road Commission topo field notes book #739.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Railroad spike on existing centerline of West Water Street pavement.

Located on the true Township line.

S 04°W 30.68' to set P.K. nail with county remon tag in E. side of power pole.

N 04°W 33.68' to set P.K. nail with county remon tag in W. side of power pole.

N 76°E 135.23' to set P.K. nail with county remon tag in S.E. side of power pole.

N 77°W 151.70' to set P.K. nail with county remon tag in N.E. side of power pole.

WEST 2632.43' to S 1/4 corner of Section 36, T7N-R16E.

EAST 2648.66' to S 1/4 corner of Section 31, T7N-R17E.


Signed by John C. Niederhauser

Surveyor's Michigan License No. 24608

PA 345-1990

PEER COMMITTEE

APPROVED 6-10-94



APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

Signed By: _____

St. Clair County Land Surveyor

Date

Surveyor's Michigan License No. _____

LIBER 007 PAGE 363