

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____ _____ _____
2. Property Controlling in Section	S 10 T 43N R 16W S 14 T 43N R 16W S _____ T _____ R _____ S _____ T _____ R _____	5 9 _____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 5 06/27/13
9 07/03/13 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(5-Sec. 10) North 1/16 corner of Section 10. Previously monumented in 1975 by Thomas P. O'Brien
PS#21274 (L1 of Surveys P91) and accepted by Dustin Taylor PS#50454 who used the O'Brien position to
control further surveys within Section 10 in 2005 and 2013. Monument noted as being a 1/2" iron
#21274.

(9-Sec. 14) East 1/16 corner of Section 14. Previously monumented and noted on prior surveys of
record as being marked by a concrete monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(5-Sec. 10) The monument of record was not recovered and appears to have been destroyed by earth-
moving or logging activity. Reestablished the O'Brien/Taylor position for the corner by measurement
and distance from H3 and I3, using information supplied by Dustin Taylor, PS. The position
reestablished lies S 00°46'14"E 1325.08' from H3 and N 00°52'19"W 1325.83' from Thomas O'Brien's
monument at the Center of Section 10 (MCS83 grid bearings and distances).

(9-Sec. 14) Found a 4" square concrete monument, in good condition, located S 89°47'30"E 1328.43'
from the monumented Center of Section 14, and N 89°49'54"W 1328.30' from the monumented Quarter
corner K6. Accepted the monument as a careful and faithful determination of the position of the
corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
10" W.Birch S02°W 69.0' mrkd "N1/16 BT"
8" Sugar S48°E 39.0' do
13" Sugar N75°E 35.45' do
9" Sugar N54°E 49.4' do
E= 8054616.718 N= 151017.880

(9) Found 4" sq. concrete monument.
Set measuring nail with MDNR tag in the side of:
10" Hemlock S21°E 15.3' mrkd "E1/16 BT"
8" Hemlock S66°E 8.35' do
7" Hemlock N12°W 8.95' do
9" Hemlock S74°W 16.05' do
E= 8056672.657 N= 148994.449

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)
Coord. Ref.=NGS PID DL6164: N= 131822.939 m. E= 8059239.498 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 08/27/2013

For the Michigan Department of Natural Resources, Forest Resources Division

