

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 13W	A4
	T R	
	T R	
2. Property Controlling in Section	S 7 T 46N R 13W	5
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 04/03/13 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established,
monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A4) Quarter corner common to Section 7 T46N-R13W and Section 12, T46N-R14W. 1841 - Established by
W.A.Burt, Deputy Surveyor on the Range line between Section corners 40.00 chains north and south.
Set post. Fir 8" S45°E 20 links, Birch 10" N45°W 15 links. Found no subsequent record.

(5-Sec. 7) North 1/16 corner, Section 7. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A4) The original post and accessories were not recovered. Found no evidence of the position of the
original corner on the ground. Reestablished the position for the corner midway and on the Range
line between Section corners 2646.46' north and south.

(5-Sec. 7) Established the position for the corner midway and on a straight line between Quarter
corner 1303.94' north and the intersection of 1/4 lines of Section 7 1303.94' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap
Set measuring nail with MDNR tag in the side of:
12" Cedar N01°W 6.1' mrkd "1/4S NBT"
6" Maple S65°E 26.55' do
9" Maple S29°W 19.05' do
7" Maple S25°E 22.65' do
E= 8077671.271 N= 179760.975

(5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
7" B.Spruce N21°E 9.65' mrkd "N1/16 BT"
8" B.Spruce N59°W 16.1' do
10" B.Spruce S14°W 10.7' do
7" Maple S68°E 30.8' do
E= 8078420.378 N= 180159.606

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).
Coord. Ref.=NGS PID RK0039: N= 173942.810m E= 8064409.357m

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/09/2013

For the Michigan Department of Natural Resources, Forest Resources Division

