

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey

T 46N R 15W

17

T 46N R 15W

62

T R

S

T R

2. Property Controlling  
in Section

S

T R

S

T R

3. Miscellaneous  
Property in Sec.

S

T R

S

T R

4. Lot No. , Recorded Plat

5. Private Claims

62 Jun 06 2006

17 Jun 07 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(17) Corner common to Sections 14-15-22-23. 1957 - Remonumented by Billy D. Buckler RLS from one Y.Birch B.T., dead but standing and in good condition. Set 1" I.pipe with 4" brass cap. 17" W.Pine S34W 135 links, 12" Hemlock S85E 43 links, 12" Hemlock N07E 37 links.  
(62) Quarter corner common to Sections 3 and 4. 1850 - According to the first transcription of the original GLO field notes this corner was established by Guy Carleton, Deputy Surveyor, on the Section line between corner G1 40.03 chains north and corner G3 40.17 2/3 chains south. According to the original GLO plat of this township, this corner is reported to be on the section line between G1 40.00 2/3 chains north and G3 40.20 chains south. The difference between the two positions is 2 1/3 links. Carleton set quarter post and made BTs: Birch 14 N68E 9 links, Beech 12 S66W 19 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(17) Recovered the 1957 monument in good condition and at record bearing and distance from the 1957 witness trees. The W.Pine is a cut stump, the Hemlock SE is standing dead, and the Hemlock NE is in good condition.

(62) The original post and accessories were not recovered. Found a 1.5" dia. iron pipe in good condition located 9.77' West of a straight line between G1 and G3 and 18.40' S. of the proportionate position based on the GLO plat, and 16.85' S. of the proportionate position based on the GLO notes. I note that corner I2 in this township, previously found, accepted and recorded by Surveyor Fluharty (L1 P145 Schoolcraft Co. LCR) is offset similarly from the proportionate position for that corner: 10.34' west and 20.95' south. This correlation suggests to me that the locations of the monuments at G2 and I2 perpetuate some scheme, which I presume represents that of the original surveyor. Accordingly, I accept the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(17) Fd. 1" ID I.pipe with 4" brass MI

Dept. of Conservation cap. Set

measuring nails in:

15" Hemlock N12E 25.51' mrkd "S14" \*

9" Maple N80E 8.3' mrkd "S14 NBT"

9" Maple N38W 13.24' "S15 NBT"

14" Hemlock S45W 24.7' "S22 NBT"

Bearings are magnetic. Distances are to nail with tag. \* denotes 1957 NBT.

(62) Fd. 1.5" dia. iron pipe. Set

measuring nails in:

6" Maple S67W 11.0' mrkd "1/4S NBT"

5" Maple N55W 12.6' do

6" Maple S38E 13.5' do

7" Maple N41E 20.18' do

Bearings are magnetic. Distances are to nail with tag.



Signed by

*Stephan J. Szyszkoski*

Date

8/15/06

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources, Office of Land and Facilities