

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Shiawassee
(County)

Located in:

Corner Code #

RECORDED

96 NOV 18 PM 3:39

REGISTER OF DEEDS

Kyle Smith
SHIAWASSEE COUNTY, MIC

1. Public Land Survey T 5N R 2E M-9
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. , Recorded Plat

5. Private Claims

I, Mark L. VanRaemdonck, in a field survey on November 6, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1.) Original: Joseph Wampler, D.S., 1826.

Monument: Wood post

Accessories: Hickory 6 S5°E 9
W. Oak 6 N34°W 8

2.) M. VanRaemdonck, L.C.R.C. recorded Liber 2, page 847, 1/8/93.

Monument: Re-established location of NE corner of Section 25, T5N-R2E, at G.L.O. jog a distance of 0.06 chains South of the

Northwest corner of Section 30, T5N-R3E

Accessories: North 3.96' R.R. spike at NW corner Section 30, T5N-RE
S30°E 53.78' P.K. in E. face util. pole
N50°E 49.07' Top cen. tel. cable box
N65°E 90.16' Set N&T S. face util. pole

3.) M. VanRaemdonck, survey recorded Liber 6, page 392, 1/8/93.

Monument: None given.

Accessories: Same as no. 2 above.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found P.K. and tag #24622 as referenced in no. 2 and no. 3 above. I accepted this location as the careful and faithful re-establishment of the original corner position based on the best available evidence. Excavation for Harrison Marker provided no further evidence. Found no conflicting evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Installed a standard Shiawassee County Harrison Marker monument at the location described above. The monument is stamped "REMON 24622" and is witnessed by the following accessories:

N60°E 54.54' Set mag nail & tag in W. face 24" Walnut
N30°W 38.92' Set mag nail & tag in W. face 10" Elm
S30°W 53.52' Set mag nail & tag in W. face util. pole
S50°W 61.18' E. edge road sign post

Signed by


Mark L. VanRaemdonck

Date

Nov. 12, 1996

Surveyor's Michigan License No. 24622

APPROVED

County Remonumentation
Peer Review GroupFORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983LIBER 1R PG 179