

SURVEY &
REMONUMENTATION

MAR 05 1998

1997 REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Indianfields Twp.

Tuscola

(County)

Located In:

Corner Code #

1. Public Land Survey

T12N R 09E

G-13

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

S

S

S

S

T

T

T

T

R

R

R

R

4. Lot No. , Recorded Plat

5. Private Claims

I, Kenneth D. Dunton, in a field survey on Sept. 5, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

March 19, 1834 Hervey Parke, D.S. Set post corner Sections 33 & 34, B. Ash 28" N80°W 18 links, Cedar 12" N30°E 44 links. March 20-24, 1900 G. B. Felton, Co. Surveyor, Survey of Section 33, T12N-R9E. SE corner section, prev. set by me from B. T.'s, cedar post & crockery at corner. Jan. 1961 M.S.H.D. witness card, E. C. Parker, Survey Chief, found 1" axle 3' deep & set 3/4" pipe above it. N28°W 54.25' cor. fenc. post, N25°E 54.79' cor. fen. post, S57°W 72.15' NE cor. hdwl., South 2.80' centerline M-46. Oct. 19, 1971 mortgage survey L-1, P-265 by Sides, L.S. #13042. No object stated. South 32.9' E. leg sign post, East 79.0' mon. box.

(Section A continued on back of form.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found boat spike in monument box and one accessory that indicates that the corner found is in the same position as the 1961 witness card. Accepted boat spike found as the best evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed standard brass cap over boat spike found in monument box. Stamped cap G-13, T12N-R9E. Encased cap in concrete in monument box. S62°W 31.17' fnd. "+" in center of Sta. 1388+00. East 78.78' fnd. 1" iron. North 9.22' to North edge of conc. pavement. South 2.80' to centerline joint E-W pavement.

Signed by

Surveyor's Michigan License No. 23503

Date

10-20-97



APPROVED

10-20-97

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1985

Section A con't from front of form:

June 28, 1983 L.C.R.C. Page 50 by Emery, L.S. #24593. Found boat spike in mon. box. N15°E 9.35' N. edge pave. @ joint, East 78.73' center mon. box cover, S10°E 14.90' S. edge pave. @ joint, South 2.8' centerline joint in pavement. June 29, 1983 surveys L-533, P-836 & 837 and L-533, P-1207 & 1208 by Emery, L.S. #24593. Object and accessories same as L.C.R.C. Page 50. Sept. 20, 1984 survey L-546, P-269 by Emery, L.S. #24593, also April 17, 1985 survey L-549, P-1455 by Emery, L.S. #24593. Object and accessories same as L.C.R.C. Page 50. August 2, 1995 survey L-677, P-1325 & 1326 by Field, L.S. #37276. Fnd. boat spike in mon. box. East 78.77' fnd. boat spike in mon. box, South 2.80' centerline M-46, North 9.23' N. edge conc. pave., South 34.23' E. edge of E. sign post leg, S65°W 31.48' center of "+" in Sta. 1388+00.

