

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Waverly Township

Van Buren County

(County)

Located In:

Corner Code #

FILED

1. Public Land Survey

T 2S R 14W

E-2

W. 1/4 Post, Sec. 4

T R

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

Nov 14 11 48 AM '95

Mark A. Smith

VAN BUREN CO.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, Donald R. Gilchrist, survey on 10/10, 19 95,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1830 - Government - George W. Harrison, D.S. - North between Sections 4 and
5 a distance of 40.00 chs. (2640.00') and set Post Corner, Witnesses: 20"
White Oak - S. 28° W. - 23 lks. (15.18'). 12" Beech - S. 39° E. - 13 lks.
(8.58'). 11/31/1899 - George Mutchler, C.S. File and Earthen (6").
Witnesses: 14" Willow - N. 77°15' West - 36 lks. (23.76'). Distance South
to Eighth Post is 20.1425 chs. (1329.40') to stake, continuing South
20.1425 chs. (1329.40') to Southwest Corner (stone and earthen) for a total
of 2658.80'. Distance North 42.095 chs. (2778.27') to Northwest corner
(stone). Continued on Reverse

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd 1/2" iron in monument box. Removed and set 20" Harrison Marker
(Slimline).

Approved at the July 5, 1995 Van Buren County Peer Group Meeting and is
accepted as a careful and faithful re-establishment of the position of the
Original Government Corner.


Ratified by Peer Group in
accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date 7/5/95 D. R. A.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Harrison Marker (Slimline) in monument box.

6" Pine - North 20° West - 63.71' pk/w on Southwest side.
P.P. - West - 30.55' pk/w on North side.
12" Walnut - East - 40.85' pk/w on North side.
Centerline North and South Road - 5' East.



Signed by Donald R. Gilchrist

Date 11/14/95

Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583

9758 11/14 0105 10 SURVEY 9:00

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

Continued

Distance East to Eighth Post is 20.21 chs. (1333.86'), and continuing East 20.21 chs. (1333.86;) to Center Quarter Post (stone) for a total of 2667.72'.

9/12/1951 - T.A. Smith, C.S. Jones and Allen Drain notes. Catch Basin is 2 rods South and 7 rods West of Northeast corner of Section 8.

1961 - Van Buren County Road Commission Plans

STA - 79 + 97

8" Elm - West - 28.0'

10" Walnut - SE - 52.0'

10/3/1972 - Dennis A. Middleton, R.L.S. (Smith C.S.).

Section 4. Recorded Survey (Liber 3 Page 26). Set Railroad Spike.

Witnesses: 60 Penny Spike in Phone Pole - SW - 70.57'; 60 Penny Spike in Phone Pole - NW - 82.78'; Corner is 5.5 ± West of Center Line of Slab; Right of Way Iron is 33' East. Distance South is 2652.19' to Section Corner. Distance North is 2778.81' to Section Corner. Distance East is 2667.72' to Center Quarter Post.

10/31/1972 - D.R. Gilchrist, R.L.S.

Recordation Certificate (Liber 1 Page 604).

Same as Recorded Survey above.