

RC 1247

LI 27015 PA 723

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wayne (County)

Located In:

Corner Code ://

- 1. Public Land Survey T 1 S R 10 E. L-13
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-7-93
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1247

I, William L. Roskelly in a field survey on October 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


A. Description of original monument and accessories and/or subsequent restoration:

No G.L.O. Witnesses remain
L.C.R.C. L. 24236 P. 881 & 882 on 2/1/89 Grant Ward found monument in monument box

- N. 46° W. 54.62' set 60d spike & disc. N.E. face of utility pole
- S. 80° W. 128.21' set 60d spike & disc. S.E. face of utility pole
- S. 45° E. 49.57' set 60d spike & disc. N.E. face of utility pole
- N. 80° E. 135.19' set 60d spike & disc. S. face of utility pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found monument box with concrete monument steel bar.
Verified section corner thru document L. 24236, Pg. 881,882.
N. 46° W. 54.62 see #5 below
S. 80° W. 128.21 see #4 below
S. 45° E. 49.57 see #3 below
N. 80° E. 135.19 see #2 below



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13: Section corner 36. Found monument box with conc. mon. steel bar at Joy & Asbury Park. The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. Placed Wayne Co. brass disk with license #10705.
Center key hole of watergate N. 38° E. dist. 44.75.
Found 60d spike & disc #22445 S. face of P. pole N. 80° E. dist. 135.30
Found 60d spike & disc. #22445 N.E. face of P. pole S. 45° E. dist. 49.71
Found 60d spike & disc #22445 S.E. face of P. pole S. 80° W. dist. 128.29
Found 60d spike & disc #22445 N.E. face of P. pole N. 46° W. dist. 54.63

Signed by *William L. Roskelly*

Date November 9, 1993

Surveyor's Michigan License No. 10705

2R 11KD

REC-7 PH 2:10