

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
Wexford \_\_\_\_\_  
(County) \_\_\_\_\_

1. Public Land Survey	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
2. Property Controlling in Section	S	30	T	24N	R	11W	12
	S	30	T	24N	R	11W	14
3. Miscellaneous Property in Section	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_  
5. Private Claims: \_\_\_\_\_


I, Craig W. McVean, in a field survey on May, 15, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

12 - None 14 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

12 - CS 1/16 Cor. Section 30  
Set 2" Alum. Cap on 5/8" x 34" iron rebar per Standard BLM procedure.  
14 - S 1/16 corner common to sections 30 & 29 -  
A 12" Cedar tree at corner position. Scribed 12" Cedar "S1/16 S30" on W. side and "S29" on E. Side per standard BLM procedure. Set 2" Alum. Cap on 5/8" x 34" rebar 50' East on line as witness corner. CL of N-S gravel road is 106' E. of corner tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

12 - 2" stamped aluminum cap on a 5/8" X 34" Rebar  
S83°E 35.12' to set nail & tag in N side 9" Ash  
S31°W 5.42' to set nail & tag in SE side 7" Ash  
N5°E 17.74' to set nail & tag in W side 12" R. Maple  
S86°W 18.91' to set nail & tag in N side 4" Ash  
Set Blue carsonite post with location tag 1' SE  
14 - 12" Cedar - Corner tree - scribed "S1/16 S 30" and "S 29" on E side. Add Loc. tag.  
2" stamped aluminum cap on the 5/8" X 34" rebar  
50' East on S1/16 line as witness corner.  
Witnesses to 2" Alum. Cap - stamped - "WC" - wit. corner  
S24°W 5.95' to nail & tag in NW side 20" Cedar  
N30°W 56.04' to set nail & tag in E side 13" Cedar  
N12°W 62.40' to set nail & tag in E side 13" Cedar  
S60°E 31.25' to set nail & tag in NE side 18" Cherry  
Set blue carsonite post with location tag 1' S

Signed by: Craig W. McVean Date: 11/10/2003  
Surveyor's Michigan License No.: 39088

Register of Deeds Stamp & File Number