

**SURVEY &  
REMONUMENTATION**

MAY 09 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
WASHTENAW COUNTY, MI

MAR 29 1 30 PM '96

For corners in

WASHTENAW (County)	Located In:	Corner Code #
1. Public Land Survey	T 1 S R 6 E	M - 10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

PEGGY J. HAINES  
COUNTY CLERK/REGISTER

*COPY -*  
Liber 00001 Page 0415 RM

*-copy-*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11			
5												
6	18		17		16		15		14			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												

I, I. JOHN JEKABSON, in a field survey on 7 November, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
1819 G.L.O. - SET POST Black Oak, 15" S 03°W 2.10 ch  
T. WAMPLER

1935 23 April WASHTENAW  
COUNTY ROAD COMMISSION  
W.J. ARMSTRONG #2444

Found a very old wood stake in the center of a group of large stones.  
Reset with an Iron Pipe with stones, bricks and broken china around it

Elm, 3"	S 80° E	104.3	1
Twin Elm (stump with sprouts)	S 70° E	29.6	2
Elm, 3"	S 27° E	60.7	3
Elm, 10"	S 15° W	104.2	4
Elm, 5'	S 23° W	38.9	5
Twin Elm, 12"	S 62° W	53.2	6
Elm, 16"	S 72° W	25.8	7
2 R. of W. Pipes			8

SEE BACK OF THIS SHEET (NEXT PAGE) FOR COMPLETE SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1"X24" IRON PIPE 2" BELOW GRAVEL SURFACE.  
When we pulled it out, we found it to be SET IN A  
1½"X36" IRON PIPE SURROUNDED BY CHINA & BRICKS.

USING 3 WITNESSES FROM SECTION "A"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

RESET 1½"X36" IRON PIPE WITH 1" IRON PIPE WIREMON CAP.	6" Ash Stump with sprouts	East	31.22	14
	C/L Dead 7" Cherry	S 85° W	13.75	17
	"Stop Ahead" Sign	S 05° W	101.20	20
	PK & RT in W sd Utility Pole	N 21° E	95.19	21
	PK & RT in SW sd 16" Cottonwood	S 62° E	84.46	22
	PK & RT in NW sd 8" Cottonwood	S 27° W	33.92	23
	PK & RT in N sd 13" Cottonwood	S 82° W	24.06	24



I conclude that after careful study of the record documentation and field observations, that this corner is a careful and faithful perpetuation of the position of the original corner.

Signed by I. John Jekabson Date 1 DECEMBER, 1995  
Surveyor's Michigan License No. 19836

