



SYMBOL LEGEND		REFERENCE POINTS				
TREE	-	R.P. #	NORTH	EAST	ELEV.	DESC.
VALVE	+	1	1000.00	1000.00	585.16	COR. CONC.
HEM = HEMLOCK		2	1411.41	1000.00	585.16	PK NAIL
O = OAK		3	1506.84	830.20	588.85	IRON
P = PINE		4	2006.04	744.95	626.56	IRON

BENCH MARK
 BM 1
 NAIL IN E. SIDE 10" PINE
 ELEVATION 587.41

WITNESSES TO R.P.

R.P. 1
 N.W. COR. CONC. TO CONTACT
 STATION (CHANNEL CAMPGROUND)

R.P. 2 (PK NAIL)
 NAIL S. SIDE 18" OAK, S85°E, 52.47'
 NAIL E. SIDE 14" OAK, N25°W, 43.74'
 NAIL N. SIDE 8" HEMLOCK, S60°W, 56.17'
 FACE OF SIGN POST, S80°W, 15.16'

REMOVE EXISTING PIPING THROUGH BERM PRIOR TO ABSORPTION BED CONSTRUCTION. BERM SHALL BE RESTORED.

EXISTING FENCE SHALL BE REMOVED PRIOR TO CONSTRUCTION AND SALVAGED. FENCE SHALL BE INSTALLED ALONG TOP OF NORTH BERM OF EXISTING LAGOON. FENCE AND POSTS WHICH ARE NOT USED SHALL BE DELIVERED TO PARK YARD.

EXISTING PUMP STATION - SEE SHEET 5 FOR DEMOLITION REQUIREMENTS.

- GENERAL NOTES**
1. WASTEWATER SERVICE SHALL BE MAINTAINED THROUGHOUT DURATION OF PROJECT.
 2. EXISTING LAGOON SHALL BE PROTECTED AT ALL TIMES DURING CONSTRUCTION.
 3. UPON COMPLETION OF THE NEW BEDS, SEPTIC TANKS, AND PUMP STATION, AND UPON RECEIVING WRITTEN APPROVAL OF PROJECT MANAGER, CONTRACTOR SHALL DRAIN AND/OR PUMP CONTENTS OF EXISTING LAGOON TO NEW WASTEWATER SYSTEM. RATE OF DISCHARGE SHALL NOT EXCEED 10,000 GPD. CONTRACTOR'S PROPOSED METHOD OF DRAINING AND/OR PUMPING OF LAGOON CONTENTS SHALL BE REVIEWED BY PROJECT MANAGER. DISCHARGE OF SLUDGE FROM THE EXISTING LAGOON TO THE NEW WASTEWATER SYSTEM WILL NOT BE ALLOWED.

FILE NO.: 115002SM
 PLOT DATE: 9-21-94
 UPDATED BY: LUS

DRN BY: DAL	IDENTIFICATION NO. PROJECT - MUSKEGON	ISSUED FOR: PRELIMINARY <input checked="" type="checkbox"/>	DATE: 7-21-94		STATE OF MICHIGAN DEPARTMENT OF MANAGEMENT AND BUDGET Office of Facilities	QUALITY OF LIFE RECREATION BOND MICHIGAN DEPARTMENT OF NATURAL RESOURCES PARKS DIVISION - STATE ACCT. NO. 607-75-2450-400	MUSKEGON STATE PARK CAMPGROUND WASTEWATER SYSTEM GENERAL SITE MAP	SCALE: 1"=40'
DESIGN BY: DAL	STATE ACCOUNT	CONSTRUCTION <input checked="" type="checkbox"/>	DATE: 9-23-94					PROJ. NO.: 91159
CHKD BY: GJF	607-75-2450-400	FINAL RECORD <input type="checkbox"/>						SHEET 2 OF 21
APP'D BY: GDA								