STAIR, WALKWAY and PARKING AREA - for MORE INFORMATION SEE STAIR ACCESS DRAWING. ALSO, EROSION CONTROL ON THE DUNES. REMOVE EXISTING SNOW FENCE and REPLACE with 3 NEW ROWS of FENCE on BOTH SIDES of DUNE. APPROXIMATELY 2 MILES OF FENCE-TOTAL. TRANSPLANT DUNE GRASS PLUGS on LAKE SIDE of DUNE. FUNDING for these PROJECTS is LIKELY to be CZM GRANT or PROPOSAL P-STEWARDSHIP MONIES. EROSION CONTROL SHOULD BE DONE WHEN, or AFTER, THE STAIR PROJECT IS COMPLETED.

ELIMINATE SITES #86, 88, 90, 92, 93 and 94.

SITES # 98, 101, 103, 105, 107, 109, 110 and 111 NEED ADDITIONAL GRAVEL DUE to SANDY SOILS.

5' WIDE CONCRETE, or BITUMINOUS, WALK FROM PARKING to TOILET BUILDING, and ON TO THE EAST CAMPGROUND DRIVE

BARRIER FREE PARKING and WALK ACCESS.

IMPROVE TOILET/SHOWER BUILDING - SEE WRITTEN INFORMATION for EXACT PROJECT SCOPE.

COMBINE SITES #65 and #67 INTO ONE.

REMOVE OLD HANDPUMP CONCRETE SLAB, CUT CASING, SEAL WELL and RESEED

REMOVE OLD HANDPUMP CONCRETE SLABS, CUT CASING, SEAL WELL and RESEED

IMPROVE CAMPGROUND TOILET/SHOWER BUILDING. SEE WRITTEN INFORMATION for EXACT PROJECT SCOPE.

NEW CAMPGROUND PLAY AREA; PLAY for 1-5 YEAR OLD SEPERATED from 5-12 YEAR OLDS. AREAS with BENCHES are PROVIDED for ADULT SUPERVISION. NATIVE LANDSCAPING to HELP PROVIDE A QUALITY EXPERIENCE.

PAVED WALKWAYS and PARKING/CAMPSITES for MINI-CABINS and BARRIER FREE VAULT TOILET and TOILET/SHOWER BUILDING.

ELIMINATE SITE #3 if CAMP OFFICE PARKING IS DEVELOPED

CAMPGROUND OFFICE PARKING LOT - 3 SPACES -- (1) BARRIER FREE SPACE

IMPROVE CAMPGROUND OFFICE - SEE WRITTEN INFORMATION FOR EXACT PROJECT SCOPE

GRASSCRETE (or EQUIVALENT POROUS PAVER) FOR WOOD VENDING TRAILER.

EXISTING PLAY EQUIPMENT and INFORMATION DISPLAY

SANITATION STATION - CONCEPT LOCATION A.

5' WIDE COMPACTED CONCRETE FINES BARRIER FREE WALK

PAVEMENT MARKINGS with PEDESTRIAN CROSSING SIGNS - TYPICAL

EXISTING VAULT TOILETS with BARRIER FREE WALK

DUMPSTER FENCE ENCLOSURE - SEE DETAIL.

SANITATION STATION - CONCEPT LOCATION B with AREA SHOWN FOR FUTURE EXPANSION.

VISITOR PARKING LOT - 38 TOTAL SPACES with (2) BARRIER FREE SPACES. LOT to be GRAVEL INITIALLY. ALSO, LOT SIZE to be SLIGHTLY LARGER than NORMAL to ALLOW for SNOW PLOWING for WINTER SPORTS COMPLEX PARKING.

Septic Tank w/2 Dosing Chambers.

LP Tank

Transformer

Mini-Cabin #1

Mini-Cabin #2

B.F. Vault Toilet

Ex. Phone

M-20

LAKE MICHIGAN CAMPGROUND

SEMI-MODERN CAMPGROUND

FUTURE IMPROVED PLAYGROUND

SPORTS COMPLEX BLDG.

Hoot

SCALE 1" = 60'

0 60'

GENERAL NOTES:

- VENDING COURT to be ADDED (Roofed Structure) to the EXISTING TOILET/SHOWER BUILDINGS for NEWSPAPERS, SODA MACHINE, PHONE and BULLETIN BOARD. ALL ADDITIONS to this, or any, PROJECT SHALL MEET ALL APPLICABLE BARRIER FREE CODES.
- ALL LOT MARKERS SHALL be REPLACED.
- CONVERT 3 BUILDINGS (2 TOILET/SHOWER BUILDINGS and SPORTS COMPLEX BUILDING) from LP to NATURAL GAS.

48 HOURS (2 WORKING DAYS) BEFORE YOU DIG CALL MISS DIG 800-482-7171 (TOLL-FREE)

SURVEYED BY		DRAWN BY P. PETERSEN	1/95	NO.	DATE	BY	REVISIONS	NO.	DATE	BY	REVISIONS	MICHIGAN DEPARTMENT OF NATURAL RESOURCES	1995 CAMPGROUND RENOVATION PROJECT SHEET TITLE
DESIGNED BY P. PETERSEN	1/95	CHECKED BY		1.				1.					
	DATE		DATE	2.				2.					

MUSKEGON - LAKE MICHIGAN CAMPGROUND — AREA OR PARK

PROPOSAL P — PROJECT

PROJECT NO.

SHEET 2 OF 2 — PLAN NO. L-129