

DRAWN BY S.J.H. 5/1/48
 TRACED BY
 CHECKED BY
 DATE
 REVISIONS
 NO. DATE BY
 1
 2
 3
 4
 5
 6
 APPROVED BY [Signature] 6/7/48
 ASSISTANT CHIEF IN CHARGE OF DESIGN DATES: 5-25-48
 REVIEWED BY SECTIONS
 ARCHITECTURAL B.H.H.
 ENGINEERING D.A.C.
 LANDSCAPE

AGGREGATE SURFACE COURSE SQ.YDS.			
AS PER PLANS	PLANS	SQ.YDS.	AS CONSTRUCTED
STA. TO STA.	LIN. FT.	6" COMPACTED	
0+84 - 11+77.8	1261.8		
12+37.3 - 18+49.1	611.8		
19+0 - 25+83.3	683.3		
23+22 - 26+04	282.0		
ENTRANCE RD. TOTAL	2838.9	6340	
0+10 - 3+43.6	333.6		
3+43.6 - 12+23.8	880.2		
CAMP AREA TOTAL	1213.8	1976	
ROAD THRU PARKING	254.5		
PARKING STRIPS	1020.0		
END CONNECTORS	217.0		
FILLETS	34.0		
PARKING AREA TOTAL	1525.5	3390	
GRAND TOTAL		11,706	

EARTHWORK CU. YDS.												
AS PER PLANS						AS CONSTRUCTED						
STA. TO STA.	EXCAVATION	BORROW	FILL	SHRINKAGE	LOSS	OVERHAUL	EXCAVATION	BORROW	FILL	SHRINKAGE	LOSS	OVERHAUL
0-84-2+25	758		594	89								
2+25-5+51.7	1320		1219	182								
5+51.7+23+22	8697		6054	909	1728	3246						
11+50-14+40	1857 (MUCK)											
ENT. RD. TOTAL	12,632		7867	1180	1728	3246						
0+10 - 3+50	213		196	25								
3+50-12+24	TURNPIKE SECTION											
CAMP AREA ROAD TOTALS	213		196	25								
PARKING AREA	995		1024	153								
OUTLET DITCH	160											
PARKING AREA TOTALS	1155		1024	153								
GRAND TOTAL	14,000		9087	1358	1728	3246						

CORRUGATED METAL PIPE LIN. FT.								
AS PER PLANS				AS CONSTRUCTED				
STATION	8"	12"	24"	36"	8"	12"	24"	36"
2+25		104						
11+60	440							
25+64			50					
0+50 (CAMP AREA)	30							

SODDING CLASS "B"		
AS PER PLANS		AS CONSTRUCTED
STA. TO STA.	SQ. YDS.	SQ. YDS.
11+60-14+40	685	
PARKING AREA CURB	120	
" CATCH BASIN	15	
TOTAL	820	

CATCH BASIN, OPEN BOTTOM, COVER "E"
PARKING AREA 1 EACH

FINEGRADING AND CLEANUP		
AS PER PLANS		AS CONSTRUCTED
LOCATION	STATIONS	STATIONS
0-84-23+22 (RD ROAD)	28.2 (ENT. RD.)	
0+10 - 3+44 (20' ROAD)	3.3 (CAMP AREA RD)	
TOTAL (20' ROAD)	31.5	
3+44 - 12+24 (2' ROAD)	9.0 (CAMP AREA RD)	
PARKING AREA	5 STA. (60' WIDTH)	

CLAY SHOULDERS 2" THICK		
AS PER PLANS		AS CONSTRUCTED
STA. TO STA.	CU. YDS.	CU. YDS.
0-84-23+22	72 (ENT. RD.)	
0+10 - 3+44	8 (CAMP AREA RD)	
TOTAL	80	

CLEARING AND GRUBBING			
AS PER PLANS		AS CONSTRUCTED	
LOCATION	LIGHT	HEAVY	
ENTRANCE ROAD	2.0 ACRES	2.2 ACRES	
CAMP AREA	1.0 "		
PARKING AREA		1.4 "	
TOTAL	3.0 "	3.6 "	

STOCK PILE		
AS PER PLANS		AS CONSTRUCTED
LOCATION	CU. YDS.	
RIGHT OF STA. 10+0	50	

TURNPIKE SECTION		
AS PER PLANS		AS CONSTRUCTED
LOCATION	STATIONS	STATIONS
12' CAMP AREA ROAD	8.8	
3+44 - 12+24		

QUANTITIES SHEET

MICHIGAN DEPARTMENT OF CONSERVATION PARKS AND RECREATION DIVISION

TAQUAMENON FALLS STATE PARK LOWER FALLS ENTRANCE ROAD

SHEET NO. 6 OF 6 PLAN NO. E-102