



NORTH SCALE 1"=50'

FOR CLARITY EXISTING UTILITY LINES ARE NOT SHOWN. EXCEPTION IS WET WELL, LAGOON & SANITATION STATION.  
 ISLAND IS TO HAVE 6" PRE-CAST CURBING AND SIDE WALK IS TO PROVIDE 6" CURB.  
 AT POINTS WHERE (H) IS SHOWN HAND-CAPPED ACCESS RAMP WILL BE PROVIDED

- 1 CONTRACTOR WILL BE RESPONSIBLE FOR BITUMINOUS SURFACING ROADS AND PARKING AREA
- 2 PARK STAFF WILL BE RESPONSIBLE FOR TREE, BRUSH AND STUMP REMOVAL.
- 3 PARK STAFF WILL REMOVE GRAVEL FROM AREAS NO LONGER NEEDING GRAVEL.
- 4 PARK STAFF WILL PLACE NEW GRAVEL BASE AND RELOCATE TEMPORARY CONTACT STATION PRIOR TO WORK OF CONTRACTOR
- 5 PARK STAFF WILL CONSTRUCT NEW CONTACT STATION, SIDE WALK, PRE-CAST CURBING, TOP SOILING, SEEDING AND REMOVAL OF UNNEEDED BIT. MAT. UPON COMPLETION OF CONTRACT.
- 6 REGIONAL ENGINEER WILL ASSIST PARK STAFF IN LAYING OUT NECESSARY WORK SO AS NOT TO DELAY CONTRACTOR'S SURFACING SCHEDULE.

REVIEWED BY: Leland Johnson Jr 7/14/77  
 IN CHARGE - PROGRAM PLANNING DATE

APPROVED BY: Jack Butlerbach 7/14/77  
 CHIEF - PARKS DIVISION DATE

SURVEYED BY	DRAWN BY HELMIC	7/12/77	NO.	DATE	BY	REVISIONS	NO.	DATE	BY	REVISIONS	MICHIGAN DEPARTMENT OF NATURAL RESOURCES	CAMPGROUND ENTRANCE	AREA OR PARK SLEEPER STATE PARK	PROJECT NO.
DESIGNED BY MITTON & HELMIC	CHECKED BY		1.				3.							
DATE		DATE	2.				4.							SHEET 1 OF 1 PLAN NO. L-113