



Notes: All Stone to be split and are to be laid horizontally. Joints to approximate 1" wide and be finished flush with stone. Mortar to be 1 part Cement to 2 parts sands with 20% lime added. Floor to be of selected stones. All log posts, beams, rafters and ceiling boards to be given 2 coats of transparent Creosote preservative.

Recommended
N.A. Raymond, 11/25/36
Assoc. Rural Architect

DEPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE And MICHIGAN DEPARTMENT OF CONSERVATION CO-OPERATING		STATE PARK DIVISION
BRANCH OF PLANNING	LUDINGTON SP #2	SHEET NO. 11 of 11
SYMBOL	SHELTER OVER WELL	FILE NO. IVD-9-001
NUMBER	HIKERS CAMP SITE	
DRAWN BY	R.B.H.	
CHECKED	DATE	DESIGNED
RECOMMENDED FOR CONSTRUCTION	DATE	SUBMITTED
DATE	DATE	APPROVED
APPROVED FOR CONSTRUCTION	DATE	DATE

7-84-H