

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Alger

(County)

Located In:

Corner Code #

1. Public Land Survey

T 47N R 17W

G9

T 47N R 17W

G11

2. Property Controlling
in Section

S

T

R

S

T

R

S

T

R

3. Miscellaneous
Property in Sec.

S

T

R

S

T

R

4. Lot No. , Recorded Plat

5. Private Claims

G9 05/01/2012

G11 04/19/2012

I, Stephan J. Szyszkoski, in a field survey on

do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G9) Corner common to Sections 21-22-27-28. 1958 - Remonumented by Billy D. Buckler RLS from two (probable) original B.T.s. Cedar, down, S43W 19 links, old blazes, no scribing; Y.Birch stump bottom N43E 3 links. Set 1" pipe with 4" brass cap. 5" Cedar S13E 33.5 links, 13" W.Pine N55W 80 links.

(G11) Corner common to Sections 27-28-33-34. 1958 - Billy D. Buckler RLS found and accepted a 2" dia. iron pipe with brass cap. Found no evidence of the original corner. 13" H.Maple N45W 54 links, 15" H.Maple East 78 links, 15" Y.Birch S24E 111 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G9) The 1958 monument was not found. The remains of the original BTs were not recovered. Remonumented the 1958 position at record bearing and distance from the 1958 witnesses. The Cedar NBT SE, now 13" DBH, is in good condition, the 13" W.Pine NBT is now standing dead. Found the point of a wood post adjacent to the remonumented corner position. Accepted the 1958 position as a careful and faithful perpetuation of the position of the original corner.

(G11) Found the 2" dia. pipe of record, with brass cap, no identifying marks, in good condition and at record bearing and distance from the remaining 1958 NBT H.Maple N45W, now 16" DBH, in good condition. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G9) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
13" Cedar S09E 22.25' mrkd "S27" 1958 NBT
7" Cedar S20W 5.45' mrkd "S28 NBT"
5" Cedar N09W 10.55' "S21 NBT"
5" Cedar N82E 15.7' "S22 NBT"
Bearings are magnetic.

(G11) Found 2" dia. I.pipe with 2" brass cap. Set measuring nail with MDNR tag in the side of:
16" Sugar N40W 36.15' mrkd "S28" 1958 NBT
10" Sugar S78E 16.95' "S34 NBT"
11" Maple S09E 6.65' do
9" Sugar N64W 26.65' "S28 NBT"
Bearings are magnetic.

Signed by

Stephan J. Szyszkoski

Date

07/26/2012

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources, Forest Resources Division

