

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Alger	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 13W	G9
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 11/29/2011 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G9) Corner common to Sections 21-22-27-28. 1995 - Remonumented under P.A. 345 for the Alger Co. Remonumentation Program by R.L.Jamross PS. Set Berntsen Mon. no. A1NB30 and made the following witnesses (to PK nails with tags): Cherry 7" S63E 54.83', Maple 11" N76E 123.53', W.Pine 6" S56W 44.33', W.Pine 8" N49W 45.71', Survey Marker sign on six foot steel post N90W 8.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G9) The 1995 monument of record was found disturbed, apparently having been struck during road maintenance. At the position of the base of the 1995 monument and in accord with the 1995 witnesses of record (all existing and in good condition), I drove a 1"ID I.pipe with plastic cap "Mich. DNR PS33986" to 6" below the sandy surface of the road, the position being near the west shoulder. The 1995 position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G9) Set 1"IDx36" I.pipe w/plastic cap stamped "Mich DNR PS 33986"  
Found PK nail with ID tag in the following:  
7" Cherry S63E 54.83' blazed and scribed  
11" Maple N76E 123.53' do  
6" W.Pine S56W 44.33' do  
8" W.Pine N49W 45.71' do  
sign post West 8.0'  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 05/22/2012  
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Resources Division