

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

For corners in

ALLEGAN (County) Located in: Corner Code #

1. Public Land Survey T 2N R13W E-1-2
T R SEQ #3
T R ALLEGAN TWP
T R

2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. , Recorded Plat
5. Private Claims

I, ARTHUR W. BRINTNALL, in a field survey on 27 AUG. 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1-2

G.L.O.

NORTH BETWEEN SECS. 4 & 5
55.50 TO S. SIDE LAKE PINE 22 COR
82.61 N. BOUNDARY AT COR IN LAKE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1-3 FND N. END FE @ S. EDGE OF DUMONT LAKE 1599.5' ± N OF E-2

SET STD A.C. MON (3/4" X 36" IRON W/CAP) @ N. END OF FE 1599.5' N. OF E-2

THIS POSITION NOT ESTABLISHED BY G.L.O.

THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED BY ALLEGAN PEER GROUP 11 AUG 98.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1-2 STD A.C. MON (3/4" X 36" IRON W/CAP)
NAIL & REMON TAG SW SIDE 4" ASH S 45° E 139.29' SEE SKETCH ON BACK
NAIL & REMON TAG NE SIDE 6" ASH S 20° E 103.22'
E. EDGE FE POST NORTH 0.25'
CENTERLINE 1" MAPLE S 85° W 10.35'
S. EDGE DUMONT LAKE NORTH 2'±

Signed by Arthur W. Brintnall
PREIN & NEWHOF

Date Sept 8, 1998

Surveyor's Michigan License No. #28407



APPROVED REMONUMENTATION CORNER

P.A. 345 OF 1990

ALLEGAN COUNTY

DATE APPROVED Aug 11, 1998
COUNTY REP. Mark E. Dyer

SHEET 1 OF 2

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

