

SURVEY  
REMONUMENTATION

APR 29 1999

SECTION

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

For corners in

Allegan

(County)

Located In:

Corner Code #

1. Public Land Survey

T4N R14W

A-8

T R

T R

T R

West 1/4 corner

Section 19

Oversiel Twp.

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

I, Steve Lampen, in a field survey on December 19, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-8

GLO - corner not monumented by the GLO

Consumers Power Co. survey - 1968

Corner not set but is shown as being mid-way A-7 to A-9 and on

Line M-7 to M-9, Town 4 North, Range 15 West

A-8 to A-7 = 2636.83

A-8 to A-9 = 2636.83

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8 Did not find any monumentation at corner. Meas. A-7 to A-9 = 5273.75

Set a 3/4"x24" Allegan County Remonumentation iron and cap mid-way A-7 to A-9 and on line between M-8 and M-9. This corner was not set by the original GLO Survey. This position is accepted as the best available evidence of the position of the corner.

Traversed 2673 ft. on road.

A-8 was approved by the Allegan County Remonumentation Peer Group on December 22, 1998.

APPROVED REMONUMENTATION CORNER

P.A. 345 OF 1990

ALLEGAN COUNTY

DATE APPROVED DEC. 22, 1998  
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 3/4"x24" Allegan County Remonumentation iron and cap on the West line of Section 24, Town 4 North, Range 15 West

Azimuth = Michigan State Plane grid direction


Power pole, remonumentation tag in W side 153° 31' 164.29

6" Ash, remonumentation tag in NW side 25° 05' 119.50

6" Ash, remonumentation tag in NW side 43° 36' 68.13

3" Ash, remonumentation tag in NW side 68° 24' 57.86

M-8, Town 4 North, Range 15 West 359° 36' 35.71



Signed by Steven Lampen

Date January 11, 1999

Surveyor's Michigan License No. 37279